

GENERAL NOTES:

- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE A COPY OF THESE APPROVED PLANS PRESENT ON THE CONSTRUCTION SITE AT ALL TIMES.
- THE CONTRACTOR SHALL ATTEND PRE-CONSTRUCTION CONFERENCE WITH SCWP PRIOR TO BEGINNING CONSTRUCTION.
- ALL APPROVALS AND PERMITS REQUIRED FOR THE CONSTRUCTION OF THIS PROJECT ARE AVAILABLE AS AN APPENDIX IN THE SPECIAL PROVISIONS. ALSO INCLUDED IS A LIST OF PERMITS THE CONTRACTOR IS RESPONSIBLE FOR PROCURING PRIOR TO CONSTRUCTION.
- ALL WORK SHALL CONFORM TO THE LATEST EDITION OF STANDARD SPECIFICATIONS FOR ROAD BRIDGE AND MUNICIPAL CONSTRUCTION CURRENT EDITION (WOOD) AND THE SKAGIT COUNTY ROAD STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY SPECIFICATIONS OR STANDARDS, THE MORE STRINGENT REQUIREMENT WILL PREVAIL. ALL REFERENCES TO "STANDARD SPECIFICATIONS" REFER TO THE MOST CURRENT EDITION OF "STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION" (WOOD) UNLESS OTHERWISE NOTED.
- THIS PROJECT MAY REQUIRE VARIOUS PERMITS AS OUTLINED IN THE PROJECT SPECIFICATIONS GENERAL PROVISIONS. ALL WORK SHALL BE PERFORMED IN A MANNER WHICH ENSURES CONFORMANCE WITH ANY PERMIT REQUIREMENTS.
- UNDERGROUND UTILITIES ARE KNOWN TO EXIST IN THE AREA OF CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONTACT THE UTILITY OWNERS FOR LOCATIONS AND TO NOTIFY THE ENGINEER PROMPTLY OF ANY CONFLICT. THE ONE-CALL NUMBER FOR UNDERGROUND UTILITIES IS: 1-800-424-5555.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE INTEGRITY OF EXISTING UTILITIES AT ALL TIMES WHICH MAY INCLUDE, BUT ARE NOT LIMITED TO, POWER, TELEPHONE, CABLE TV, AND FIBER.
- THE CONTRACTOR SHALL NOTIFY PROPERTY OWNERS 48 HOURS IN ADVANCE OF ANY WORK AFFECTING ACCESS OR SERVICE AND SHALL MINIMIZE INTERRUPTIONS TO DRIVEWAYS FOR PROPERTY OWNERS ADJACENT TO THE PROJECT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL IN ACCORDANCE WITH THE CURRENT EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) INCLUDING THE WASHINGTON STATE MODIFICATIONS TO THE MUTCD PRIOR TO DISRUPTION OF ANY TRAFFIC. THE CONTRACTOR MAY CHOOSE TO ADOPT THE TRAFFIC CONTROL PLANS PROVIDED IN THIS PLAN SET OR SUBMIT AN ALTERNATIVE TRAFFIC CONTROL PLAN. TRAFFIC CONTROL PLANS MUST BE APPROVED BY SCWP AND WSDOT FOR APPROVAL. THIS APPROVAL TAKES TIME AND NO WORK SHALL COMMENCE UNTIL PLANS ARE APPROVED AND ALL APPROVED TRAFFIC CONTROL IS IN PLACE.
- PUBLIC RIGHTS-OF-WAY SHALL BE KEPT IN A CLEAN AND SERVICEABLE CONDITION AT ALL TIMES. ALL DEBRIS OR MATERIALS ARE INADVERTENTLY DEPOSITED ON ROADWAYS, THE MATERIAL SHALL BE PROMPTLY REMOVED.
- ALL LAWN AND VEGETATED AREAS OUTSIDE THE PROJECT LIMITS DISTURBED BY CONSTRUCTION EQUIPMENT, VEHICLES OR PERSONNEL SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER, AT THE CONTRACTOR'S EXPENSE.

CONSTRUCTION SWPPP NOTES:

- APPROVAL OF THIS EROSION/SEDIMENTATION CONTROL (ESC) PLAN DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT OR TEMPORARY DESIGN (E.G. SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES).
- THE IMPLEMENTATION OF THIS TESC PLAN AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPDATING OF THESE TESC BMPs IS THE RESPONSIBILITY OF THE PERMIT HOLDER UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- CONTRACTOR SHALL CLEARLY FLAG THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- CONSTRUCT THE TESC BMPs SHOWN ON THIS PLAN IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS.
- THE TESC BMPs SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, UPGRADE THESE ESC BMPs AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
- THE PERMIT HOLDER SHALL INSPECT THE ESC BMPs DAILY AND MAINTAIN THEM AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- INSPECT AND MAINTAIN THE TESC BMPs ON INACTIVE SITES A MINIMUM OF ONCE A MONTH OR WITHIN THE 48 HOURS FOLLOWING A MAJOR STORM EVENT (I.E. A 24-HOUR STORM EVENT WITH A 10-1R OR GREATER REQUIREMENT INTERVAL).
- AT NO TIME SHALL THE SEDIMENT EXCEED 80-PERCENT OF THE SUMP DEPTH OR HAVE LESS THAN 6-INCHES OF CLEARANCE FROM THE SEDIMENT SURFACE TO THE INVERT OF THE LOWEST PIPE. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM.
- INSTALL STABILIZED CONSTRUCTION ENTRANCES AT THE BEGINNING OF CONSTRUCTION AND MAINTAIN FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

ENVIRONMENTAL NOTES:

- A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE PREPARED BY THE CONTRACTOR IN COMPLIANCE WITH THE DOE STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON ADDRESSING, AND THE WESTERN WASHINGTON HYDROLOGY MANUAL ADDRESSING ALL APPLICABLE MINIMUM REQUIREMENTS. THE AREAS OF NEW AND/OR REPLACED IMPERVIOUS SURFACE SHALL BE INCLUDED IN THE SWPPP. THE CONTRACTOR SHALL SUBMIT THE SWPPP FOR THE ENGINEER'S APPROVAL BEFORE ANY WORK BEGINS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
- THE CONTRACTOR SHALL PREPARE A SPILL PREVENTION, CONTROL AND CONTAINER MEASURES (SPCC) PLAN THAT SATISFIES THE CURRENT WSDOT CONCRETE CRUSHED SURFACING TOP COURSE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) REQUIREMENTS. THE PLAN WILL BE REVIEWED AND APPROVED PRIOR TO COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTING, MAINTAINING, & REMOVING EROSION CONTROL MEASURES (SILT FENCE, ROCK CHECK DAMS, SILT PONDS, CATCH BASIN FILTERS, ETC.) THROUGHOUT THE DURATION OF THE PROJECT. ALL REMOVAL OF EROSION CONTROL WORK IS CONSIDERED INCIDENTAL TO THE ITEMS OF WORK IN THE CONTRACT FOR THIS PROJECT. REFER TO THE STORM WATER POLLUTION PREVENTION PLAN AND BID ITEMS NOTED IN THE CONTRACT PORTION OF THE PROJECT SPECIFICATIONS FOR SPECIFIC EROSION CONTROL NOTES.

ABBREVIATIONS

ABT	ABOUT	EVCE	END VERTICAL CURVE ELEVATION	OFF	OUTSIDE DIAMETER	SPCC	SPILL PREVENTION CONTROL MEASURES
ALUM	ALUMINUM	EVCS	END VERTICAL CURVE STATION	OHM	OHMS FENCING	SPL	SPLICE
AP	ANGLE POINT	EX	EXISTING	OPP	OPPOSITE	SQ	SQUARE
ACKA	AMMONIACAL COPPER ZINC ARSENATE	FFN	FOUNDATION FINISH	PC	POINT OF CURVATURE	ST	STATION
BK	BACK	FF	FINISHED FLOOR FINISH	POB	POINT OF BEGINNING	STD	STANDARD
BMP	BEST MANAGEMENT PRACTICE	FND	FOUND	POC	POINT ON CURVE	SWPPP	STORMWATER POLLUTION PREVENTION PLAN
BTWN	BETWEEN	FT	FEET	POE	POINT OF ENDING	SY	SQUARE YARD
BVCS	BEGIN VERTICAL CURVE ELEVATION	FT	FEET	PNT	POINTS PER CUBIC FOOT	SYMM	SYMMETRICAL
BVCE	BEGIN VERTICAL CURVE STATION	IE	INVERT ELEVATION	PCF	POINTS PER CUBIC FOOT	TCE	TEMPORARY CONSTRUCTION EASEMENT
CL	CLASS	INT	INTERIOR	PSI	POINT OF REVERSE CURVE	TEMP	TEMPORARY
C/L	CENTERLINE	HMA	HOT MIX ASPHALT	PT	POINT OF TANGENT	TYP	TYPICAL
CLR	CLEAR, CLEARANCE	JOINT	JOINT	PVC	POLYVINYL CHLORIDE	VC	VERTICAL CURVE
OMP	CORRUGATED METAL PIPE	JT	JOINT	PVM	PAVEMENT	VER	VERTICAL
CONC	CONCRETE	LB	POUND	R	RADIUS	VPI	VERTICAL POINT OF INTERSECTION
CONST	CONSTRUCTION	LF	LINEAR FEET	RDMWY	ROADWAY	VER	VERTICAL
CSTC	CRUSHED SURFACING TOP COURSE	LONGIT	LONGITUDINAL	REF	REFERENCE	VPI	VERTICAL POINT OF INTERSECTION
CSWGP	CONSTRUCTION STORMWATER GENERAL PERMIT	LS	LUMP SUM, LOW SHRINKAGE	REINFC	REINFORCING REQUIRED	USPS	UNITED STATES POSTAL SERVICE
CY	CUBIC YARD	LT	LEFT	REQD	RADIUS POINT	W/	WITH
DIAM, Ø	DIAMETER	MAX	MAXIMUM	RR	RAILROAD	WSDOT	WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
DIP	DUCTILE IRON PIPE	MATL	MATERIAL	RT	RIGHT	X-	CROSS
DWG	DRAWING	MIN	MINIMUM	R/W	RIGHT OF WAY	YR	YEAR
DWL	DOWNSTREAM	MUTCD	MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES	SCHED	SCHEDULE		
DIAPHRAGM	DIAPHRAGM	NO	NUMBER	SCWP	SKAGIT COUNTY PUBLIC WORKS		
E	EASTING	NPDES	NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM	SF	SHOULDER		
EA	EACH			SHT	SHEET		
EG	EXISTING GROUND ELEVATION & SEDIMENT CONTROL	NTS	NOT TO SCALE	SIM	SIMILAR		
EL ELEV	ELEVATION			SKH HD	COUNTERSUNK HEAD		
ESC	EROSION & SEDIMENT CONTROL			SLOP	SLOPE		
				SPA	SPACE		

CONCRETE SAUK VALLEY ROAD ALIGNMENT TABLE

NO.	RADIUS	LENGTH	LINE/CHORD BEARING	DELTA	START STATION	END STATION	START COORDINATE	END COORDINATE
C1	190.00'	151.97'	N33°48'28"W	45°49'35"	100+00.00	101+51.97	N=526,242.9 E=1,454,214.5	N=526,365.8E=1,454,132.1
L1		248.03'	N12°16'16"W		101+51.97	104+00.00	N=526,365.8 E=1,454,132.1	N=526,608.2 E=1,454,079.4

S. OSTERMAN CREEK DESIGN ALIGNMENT TABLE

NO.	RADIUS	LENGTH	LINE/CHORD BEARING	DELTA	START STATION	END STATION	START COORDINATE	END COORDINATE
L2		26.21'	N39°26'56"E		220+00.00	219+73.79	N=526,310.5 E=1,453,997.5	N=526,330.7 E=1,454,014.2
C2	92.03'	60.45'	N58°16'06"E	37°38'20"	219+73.79	219+13.34	N=526,330.7 E=1,454,014.2	N=526,361.9E=1,454,064.7
L3		0.33'	N77°05'16"E		219+13.34	219+13.01	N=526,361.9 E=1,454,064.7	N=526,362.0 E=1,454,065.0
C3	22.15'	13.47'	N59°39'55"E	34°50'42"	219+13.01	218+99.54	N=526,362.0 E=1,454,065.0	N=526,368.7E=1,454,076.5
L4		29.95'	N42°14'34"E		218+99.54	218+69.58	N=526,368.7 E=1,454,076.5	N=526,390.9 E=1,454,096.6
C4	25.00'	15.48'	N59°59'10"E	35°29'11"	218+69.58	218+54.10	N=526,390.9 E=1,454,096.6	N=526,398.5E=1,454,109.8
L5		57.36'	N77°43'45"E		218+54.10	217+96.74	N=526,398.5 E=1,454,109.8	N=526,410.7 E=1,454,165.8
C5	51.38'	50.60'	N49°30'49"E	56°25'52"	217+96.74	217+46.14	N=526,410.7 E=1,454,165.8	N=526,442.2E=1,454,202.8
L6		1.85'	N21°17'53"E		217+46.14	217+44.29	N=526,442.2 E=1,454,202.8	N=526,443.9 E=1,454,203.5
C6	22.32'	5.42'	N28°15'18"E	13°54'49"	217+44.29	217+38.87	N=526,443.9 E=1,454,203.5	N=526,448.7E=1,454,206.0

S. OSTERMAN CREEK DESIGN ALIGNMENT TABLE (CONT.)

NO.	RADIUS	LENGTH	LINE/CHORD BEARING	DELTA	START STATION	END STATION	START COORDINATE	END COORDINATE
L7		1.20'	N35°12'42"E		217+38.87	217+37.68	N=526,448.7 E=1,454,206.0	N=526,449.7 E=1,454,206.7
C7	50.00'	69.82'	N75°12'53"E	80°00'21"	217+37.68	216+67.86	N=526,448.7 E=1,454,206.7	N=526,466.1E=1,454,268.9
L8		19.69'	S64°46'57"E		216+67.86	216+48.17	N=526,466.1 E=1,454,268.9	N=526,457.7 E=1,454,286.7
C8	61.07'	52.53'	S40°08'18"E	49°17'18"	216+48.17	215+95.63	N=526,457.7 E=1,454,286.7	N=526,418.8E=1,454,319.5
L9		3.43'	S15°29'39"E		215+95.63	215+92.20	N=526,418.8 E=1,454,319.5	N=526,415.5 E=1,454,320.4
C9	29.76'	33.69'	S47°55'26"E	64°51'33"	215+92.20	215+58.51	N=526,415.5 E=1,454,320.4	N=526,394.1E=1,454,344.1
L10		1.85'	S80°21'12"E		215+58.51	215+56.66	N=526,394.1 E=1,454,344.1	N=526,393.8 E=1,454,345.9
C10	20.00'	20.06'	N70°54'40"E	57°28'16"	215+56.66	215+36.60	N=526,393.8 E=1,454,345.9	N=526,400.0E=1,454,364.1
L11		46.71'	N42°10'32"E		215+36.60	214+89.89	N=526,400.0 E=1,454,364.1	N=526,434.7 E=1,454,395.5



SKAGIT COUNTY PUBLIC WORKS

1800 CONTINENTAL PLACE
SEASIDE, WA 98273-6625
(360) 416-4400

NO.	DATE	REVISIONS

PROJECT NO. ECT245
DESIGNED BY: R.S.E. / APPROVED BY: R.W.
CHECKED BY: R.S.E. / APPROVED BY: R.W.

PROJECT LOCATED NEAR:
CONCRETE, WA
S 141.341918 E

GENERAL NOTES & ABBREVIATIONS

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
2 OF 30

CONSTRUCTION STORMWATER POLLUTION PREVENTION (SWPPP) ELEMENTS:

- ELEMENT 1 – PRESERVE VEGETATION/MARK CLEARING LIMITS
 - a. BEFORE BEGINNING LAND-DISTURBING ACTIVITIES, INCLUDING CLEARING AND GRADING, CLEARLY MARK ALL CLEARING LIMITS, SENSITIVE AREAS AND THEIR BUFFERS, AND TREES THAT ARE TO BE PRESERVED WITHIN THE CONSTRUCTION AREA.
 - b. RETAIN THE DUFF LAYER, NATIVE TOPSOIL, AND NATURAL VEGETATION IN AN UNDISTURBED STATE TO THE MAXIMUM DEGREE PRACTICABLE.
- ELEMENT 2 – ESTABLISH CONSTRUCTION ACCESS
 - a. LIMIT CONSTRUCTION VEHICLE ACCESS AND EXIT TO ONE ROUTE, IF POSSIBLE.
 - b. STABILIZE ACCESS POINTS WITH A PAD OF QUARRY SPALLS, CRUSHED ROCK, OR OTHER EQUIVALENT BMPs, TO MINIMIZE TRACKING SEDIMENT ONTO PUBLIC ROADS.
 - c. LOCATE WHEEL WASH OR THE BATH ON SITE, IF THE STABILIZED CONSTRUCTION ENTRANCE IS NOT EFFECTIVE IN PREVENTING TRACKING SEDIMENT ONTO PUBLIC ROADS.
 - d. IF SEDIMENT IS TRACKED OFF SITE, CLEAN THE AFFECTED ROADWAY THOROUGHLY AT THE END OF EACH DAY, OR MORE FREQUENTLY AS NECESSARY (FOR EXAMPLE, DURING WET WEATHER). REMOVE SEDIMENT FROM ROADS BY SHOVELING, SWEEPING, OR PICKUP AND TRANSPORT OF THE SEDIMENT TO A CONTROLLED SEDIMENT DISPOSAL AREA.
 - e. CONDUCT STREET WASHING ONLY AFTER SEDIMENT REMOVAL, IN ACCORDANCE WITH 2.4 ABOVE.
 - f. CONTROL STREET WASH WASTEWATER BY PLUMBING BACK ON SITE OR OTHERWISE PREVENTING IT FROM DISCHARGING INTO SYSTEMS TRIBUTARY TO WATERS OF THE STATE.
- ELEMENT 3 – CONTROL FLOW RATES
 - a. PROTECT PROPERTIES AND WATERWAYS DOWNSTREAM OF DEVELOPMENT SITES FROM EROSION AND THE ASSOCIATED DISCHARGE OF TURBID WATERS DUE TO INCREASES IN THE VELOCITY AND PEAK VOLUMETRIC FLOW RATE OF STORMWATER RUNOFF FROM THE PROJECT SITE, AS REQUIRED BY LOCAL PLAN APPROVAL AUTHORITY.
 - b. WHERE NECESSARY TO COMPLY WITH 3.a (ABOVE), CONSTRUCT STORMWATER INFILTRATION OR DETENTION BMPs AS ONE OF THE FIRST STEPS IN GRADING. ASSURE THAT DETENTION BMPs FUNCTION PROPERLY BEFORE CONSTRUCTING SITE IMPROVEMENTS (E.G., IMPERVIOUS SURFACES).
 - c. IF PERMANENT INFILTRATION PONDS ARE USED FOR FLOW CONTROL DURING CONSTRUCTION, PROTECT THESE FACILITIES FROM SILTATION DURING THE CONSTRUCTION PHASE.
- ELEMENT 4 – INSTALL SEDIMENT CONTROLS
 - a. THE PERMITTEE MUST DESIGN, INSTALL AND MAINTAIN EFFECTIVE EROSION CONTROLS AND SEDIMENT CONTROLS TO MINIMIZE THE DISCHARGE OF POLLUTANTS. AT A MINIMUM, THE PERMITTEE MUST DESIGN, INSTALL AND MAINTAIN SUCH CONTROLS TO:
 - o. CONSTRUCT SEDIMENT CONTROL BMPs (SEDIMENT PONDS, TRAPS, FILTERS, INFILTRATION FACILITIES, ETC.) AS ONE OF THE FIRST STEPS IN GRADING. THESE BMPs MUST BE FUNCTIONAL BEFORE OTHER LAND DISTURBING ACTIVITIES TAKE PLACE.
 - o. MINIMIZE SEDIMENT DISCHARGES FROM THE SITE. THE DESIGN, INSTALLATION, AND MAINTENANCE OF EROSION AND SEDIMENT CONTROLS MUST ADDRESS FACTORS SUCH AS THE AMOUNT, FREQUENCY, INTENSITY AND DURATION OF THE PRECIPITATION; THE NATURE OF RESULTING STORMWATER RUNOFF; AND SOIL CHARACTERISTICS, INCLUDING THE RANGE OF SOIL PARTICLE SIZES EXPECTED TO BE PRESENT ON THE SITE.
 - o. DIRECT STORMWATER RUNOFF FROM DISTURBED AREAS THROUGH A SEDIMENT POND OR OTHER APPROPRIATE SEDIMENT REMOVAL BMP BEFORE THE RUNOFF LEAVES A CONSTRUCTION SITE OR BEFORE DISCHARGE TO AN INFILTRATION FACILITY. RUNOFF FROM FULLY STABILIZED AREAS MAY BE DISCHARGED WITHOUT A SEDIMENT REMOVAL BMP BUT MUST CONTROL FLOW RATES PER ELEMENT 3: CONTROL FLOW RATES.
 - o. LOCATE BMPs INTENDED TO TRAP SEDIMENT ON SITE IN A MANNER TO AVOID INTERFERENCE WITH THE MOVEMENT OF JUVENILE SALMONIDS ATTEMPTING TO ENTER OFF-CHANNEL AREAS OR DRAINAGES.
 - o. PROVIDE AND MAINTAIN NATURAL BUFFERS AROUND SURFACE WATERS, DIRECT STORMWATER TO VEGETATED AREAS TO INCREASE SEDIMENT REMOVAL AND MAXIMIZE STORMWATER INFILTRATION, UNLESS INFEASIBLE.
 - o. WHERE FEASIBLE, DESIGN OUTLET STRUCTURES THAT WITHDRAW IMPOUNDED STORMWATER FROM THE SURFACE TO AVOID DISCHARGING SEDIMENT THAT IS STILL SUSPENDED LOWER IN THE WATER COLUMN.
- ELEMENT 5 – STABILIZE SOILS
 - a. THE PERMITTEE MUST STABILIZE EXPOSED AND UNWORKED SOILS BY APPLICATION OF EFFECTIVE BMPs THAT PREVENT MINOR APPLICATION OF POLLUTANTS, BUT ARE NOT LIMITED TO: TEMPORARY AND PERMANENT SEEDING, SODDING, MULCHING, PLASTIC COVERING, EROSION CONTROL FABRICS AND MATTING, SOIL APPLICATION OF POLYACRYLAMIDE (PAM), THE EARLY APPLICATION OF GRAVEL BASE ON AREAS TO BE PAVED, AND DUST CONTROL.
 - b. THE PERMITTEE MUST CONTROL STORMWATER VOLUME AND VELOCITY WITHIN THE SITE TO MINIMIZE SOIL EROSION.
 - c. THE PERMITTEE MUST CONTROL STORMWATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND TOTAL STORMWATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND TO MINIMIZE DOWNSTREAM CHANNEL AND STREAM BANK EROSION.
 - d. DEPENDING ON THE GEOGRAPHIC LOCATION OF THE PROJECT, THE PERMITTEE MUST NOT ALLOW SOILS TO REMAIN EXPOSED AND UNWORKED FOR MORE THAN THE TIME PERIODS SET FORTH BELOW TO PREVENT EROSION:
 - o. WEST OF THE CASCADE MOUNTAINS CREST DURING THE DRY SEASON (MAY 1 – SEPTEMBER 30): 7 DAYS DURING THE WET SEASON (OCTOBER 1 – APRIL 30): 2 DAYS
 - o. EAST OF THE CASCADE MOUNTAINS CREST, EXCEPT FOR CENTRAL BASIN* DURING THE DRY SEASON (JULY 1 – SEPTEMBER 30): 10 DAYS DURING THE WET SEASON (OCTOBER 1 – APRIL 30): 5 DAYS
 - o. THE CENTRAL BASIN*, EAST OF THE CASCADE MOUNTAINS CREST DURING THE DRY SEASON (JULY 1 – SEPTEMBER 30): 30 DAYS DURING THE WET SEASON (OCTOBER 1 – JUNE 30): 15 DAYS *NOTE** THE CENTRAL BASIN IS DEFINED AS THE PORTIONS OF EASTERN WASHINGTON WITH MEAN ANNUAL PRECIPITATION OF FEWER THAN 12 INCHES.
 - e. THE PERMITTEE MUST STABILIZE SOILS AT THE END OF THE SHIFT BEFORE A HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST.
 - f. THE PERMITTEE MUST STABILIZE SOIL STOCKPILES FROM EROSION, PROTECTED WITH SEDIMENT TRAPPING MEASURES, AND WHERE POSSIBLE, BE LOCATED AWAY FROM STORM DRAIN INLETS, WATERWAYS, AND DRAINAGE CHANNELS.
 - g. THE PERMITTEE MUST MINIMIZE THE AMOUNT OF SOIL EXPOSED DURING CONSTRUCTION ACTIVITY.
 - h. THE PERMITTEE MUST MINIMIZE THE DISTURBANCE OF STEEP SLOPES.
 - i. THE PERMITTEE MUST MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.

- ELEMENT 6 – PROTECT SLOPES
 - a. THE PERMITTEE MUST DESIGN AND CONSTRUCT CUT-AND-FILL SLOPES IN A MANNER TO MINIMIZE EROSION. APPLICABLE PRACTICES INCLUDING, BUT ARE NOT LIMITED TO, REDUCING CONTINUOUS LENGTH OF SLOPE WITH TERRACING AND DIMENSIONING, REDUCING SLOPE STEEPNESS, AND ROUGHENING SLOPE SURFACES (FOR EXAMPLE, TRACK WALKING).
 - b. THE PERMITTEE MUST DIVERT OFF-SITE STORMWATER (RUN-ON) OR GROUNDWATER AWAY FROM SLOPES AND DISTURBED AREAS WITH INTERCEPTOR DIKES, PILES, AND/OR SWALES. OFF-SITE STORMWATER SHOULD BE MANAGED SEPARATELY FROM STORMWATER GENERATED ON THE SITE.
 - c. AT THE TOP OF SLOPES, COLLECT DRAINAGE IN PIPE SLOPE DRAINS OR PROTECTED CHANNELS TO PREVENT EROSION.
 - i. WEST OF THE CASCADE MOUNTAINS CREST: TEMPORARY PIPE SLOPE DRAINS MUST HANDLE THE PEAK 10-MINUTE FLOW RATE FROM A TYPE 1A, 10-YEAR, 24-HOUR FREQUENCY STORM FOR THE DEVELOPED CONDITION. ALTERNATIVELY, THE 10-YEAR, 1-HOUR FLOW RATE PREDICTED BY AN APPROVED CONTINUOUS RUNOFF MODEL, INCREASED BY A FACTOR OF 1.4, MAY BE USED. THE HYDROLOGIC ANALYSIS MUST USE THE EXISTING LAND COVER CONDITION FOR PREDICTING FLOW RATES FROM TRIBUTARY AREAS OUTSIDE THE PROJECT LIMITS. FOR TRIBUTARY AREAS ON THE PROJECT SITE, THE ANALYSIS MUST USE THE TEMPORARY OR PERMANENT PROJECT LAND COVER CONDITION, WHICHEVER WILL PRODUCE THE HIGHEST FLOW RATES. IF USING THE WESTERN WASHINGTON HYDROLOGY MODEL (WHWM) TO PREDICT FLOWS, BARE SOIL AREAS SHOULD BE MODELED AS "LANDSCAPED AREA."
 - ii. EAST OF THE CASCADE MOUNTAINS CREST: TEMPORARY PIPE SLOPE DRAINS MUST HANDLE THE EXPECTED PEAK FLOW RATE FROM A 6-MONTH, 3-HOUR STORM FOR THE DEVELOPED CONDITION, REFERRED TO AS THE SHORT DURATION STORM.
 - d. PLACE EXCAVATED MATERIAL ON THE UPHILL SIDE OF TRENCHES, CONSISTENT WITH SAFETY AND SPACE CONSIDERATIONS.
 - e. PLACE CHECK DAMS AT REGULAR INTERVALS WITHIN CONSTRUCTED CHANNELS THAT ARE CUT DOWN A SLOPE.
 - f. PROTECT ALL STORM DRAIN INLETS MADE OPERABLE DURING CONSTRUCTION SO THAT STORMWATER RUNOFF DOES NOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR TREATED TO REMOVE SEDIMENT.
 - g. CLEAN OR REMOVE AND REPLACE INLET PROTECTION DEVICES WHEN SEDIMENT HAS FILLED ONE-THIRD OF THE AVAILABLE STORAGE (UNLESS A DIFFERENT STANDARD IS SPECIFIED BY THE PRODUCT MANUFACTURER).
- ELEMENT 8 – STABILIZE CHANNELS AND OUTLETS
 - a. DESIGN, CONSTRUCT, AND STABILIZE ALL ON-SITE CONVEYANCE CHANNELS TO PREVENT EROSION FROM THE FOLLOWING EXPECTED PEAK FLOWS:
 - i. WEST OF THE CASCADE MOUNTAINS CREST: CHANNELS MUST HANDLE THE PEAK 10-MINUTE FLOW RATE FROM A TYPE 1A, 10-YEAR, 24-HOUR FREQUENCY STORM FOR THE DEVELOPED CONDITION. ALTERNATIVELY, THE 10-YEAR, 1-HOUR FLOW RATE INDICATED BY AN APPROVED CONTINUOUS RUNOFF MODEL, INCREASED BY A FACTOR OF 1.6, MAY BE USED. THE HYDROLOGIC ANALYSIS MUST USE THE EXISTING LAND COVER CONDITION FOR PREDICTING FLOW RATES FROM TRIBUTARY AREAS OUTSIDE THE PROJECT LIMITS. FOR TRIBUTARY AREAS ON THE PROJECT SITE, THE ANALYSIS MUST USE THE TEMPORARY OR PERMANENT PROJECT LAND COVER CONDITION, WHICHEVER WILL PRODUCE THE HIGHEST FLOW RATES. IF USING THE WHWM TO PREDICT FLOWS, BARE SOIL AREAS SHOULD BE MODELED AS "LANDSCAPED AREA."
 - ii. EAST OF THE CASCADE MOUNTAINS CREST: CHANNELS MUST HANDLE THE EXPECTED PEAK FLOW RATE FROM A 6-MONTH, 3-HOUR STORM FOR THE DEVELOPED CONDITION, REFERRED TO AS THE SHORT DURATION STORM.
 - b. PROVIDE STABILIZATION, INCLUDING ARMORING MATERIAL, ADEQUATE TO PREVENT EROSION OF OUTLETS, ADJACENT STREAM BANKS, SLOPES, AND DOWNSTREAM REACHES AT THE OUTLETS OF ALL CONVEYANCE SYSTEMS.
- ELEMENT 9 – CONTROL POLLUTANTS
 - a. DESIGN, INSTALL, IMPLEMENT, AND MAINTAIN EFFECTIVE POLLUTION PREVENTION MEASURES TO MINIMIZE THE DISCHARGE OF POLLUTANTS. THE PERMITTEE MUST:
 - o. HANDLE AND DISPOSE OF ALL POLLUTANTS, INCLUDING WASTE MATERIALS AND DEMOLITION DEBRIS THAT OCCUR ON SITE IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF STORMWATER.
 - o. PROVIDE COVER, CONTAINMENT, AND PROTECTION FROM VANDALISM FOR ALL CHEMICALS, LIQUID PRODUCTS, PETROLEUM PRODUCTS, AND OTHER MATERIALS THAT HAVE THE POTENTIAL TO POSE A THREAT TO HUMAN HEALTH OR THE ENVIRONMENT. ON-SITE FUELING TANKS MUST INCLUDE SECONDARY CONTAINMENT. SECONDARY CONTAINMENT MEANS PLACING TANKS OR CONTAINERS WITHIN AN IMPROVED STRUCTURE CAPABLE OF CONTAINING 110% OF THE VOLUME CONTAINED IN THE LARGEST TANK WITHIN THE CONTAINMENT STRUCTURE. DOUBLE- WALLED TANKS DO NOT REQUIRE ADDITIONAL SECONDARY CONTAINMENT.
 - o. CONDUCT MAINTENANCE, FUELING, AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES USING SPILL PREVENTION AND CONTROL MEASURES. CLEAN CONTAMINATED SURFACES IMMEDIATELY FOLLOWING ANY SPILL INCIDENT.
 - o. DISCHARGE WHEEL WASH OR TIRE BATH WASTEWATER TO A SEPARATE ON-SITE TREATMENT SYSTEM THAT PREVENTS DISCHARGE TO SURFACE WATER, SUCH AS CLOSED-LOOP RECIRCULATION OR UPLAND LAND APPLICATION, OR TO THE SANITARY SEWER WITH LOCAL SEWER DISTRICT APPROVAL.
 - o. APPLY FERTILIZERS AND PESTICIDES IN A MANNER AND AT APPLICATION RATES THAT WILL NOT RESULT IN LOSS OF CHEMICAL TO STORMWATER RUNOFF. FOLLOW MANUFACTURERS' LABEL REQUIREMENTS FOR APPLICATION RATES AND PROCEDURES.
 - b. USE BMPs TO PREVENT CONTAMINATION OF STORMWATER RUNOFF BY pH-MODIFYING SOURCES, THE SOURCES FOR THIS CONTAMINATION INCLUDE, BUT ARE NOT LIMITED TO: BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHOUT WATERS, AND CEMENT WATERS. STORED CONCRETE STOCKPILES, WASTE STREAMS, DEBRIS FROM CONCRETE GRINDING AND SAWING, EXPOSED AGGREGATE PROCESSES, DEWATERING CONCRETE VAULTS, CONCRETE PUMPING, AND MIXER WASHOUT WATERS.
 - c. ADJUST THE pH OF STORMWATER OR AUTHORIZED NON-STORMWATER IF NECESSARY TO PREVENT AN EXCEEDANCE OF GROUNDWATER AND/OR SURFACE WATER QUALITY STANDARDS.
 - d. ASSURE THAT WASHOUT OF CONCRETE TRUCKS IS PERFORMED OFF-SITE OR IN DESIGNATED CONCRETE WASHOUT AREAS ONLY. DO NOT WASH OUT CONCRETE TRUCK DRUMS OR CONCRETE HANDLING EQUIPMENT ONTO THE GROUND, OR INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS. WASHOUT OF CONCRETE HANDLING EQUIPMENT MAY BE PERFORMED IN DESIGNATED CONCRETE WASHOUT AREA OR IN A FORMED AREA AWAITING CONCRETE WHERE IT WILL NOT CONTAMINATE SURFACE OR GROUNDWATER. CONCRETE WASHOUT AREAS SHOULD BE DESIGNED CONCRETE WASHOUT AREAS. CONCRETE SPILLAGE OR CONCRETE DISCHARGE DIRECTLY TO GROUNDWATER OR SURFACE WATERS OF THE STATE IS PROHIBITED. DO NOT WASH OUT TO FORMED AREAS AWAITING LID FACILITIES.
 - e. OBTAIN WRITTEN APPROVAL FROM ECOLOGY BEFORE USING ANY CHEMICAL TREATMENT, EXCEPT FOR CO2, DRY ICE, OR FOOD GRADE VINEGAR TO ADJUST pH.

- j. UNCONTAMINATED WATER FROM WATER-ONLY BASED SHAFT DRILLING FOR CONSTRUCTION OF BUILDING, ROAD, AND BRIDGE FOUNDATIONS MAY BE INFILTRATED PROVIDED THE WASTEWATER IS MANAGED IN A WAY THAT PROHIBITS DISCHARGE OF SURFACE WATERS, PRIOR TO INFILTRATION, WATER FROM WATER-ONLY BASED SHAFT DRILLING THAT COMES INTO CONTACT WITH CURING CONCRETE MUST BE NEUTRALIZED UNTIL pH IS IN THE RANGE OF 6.5 TO 8.5 (SU).

ELEMENT 10 – CONTROL DEWATERING

- a. PERMITTEES MUST DISCHARGE FOUNDATION, VAULT, AND TRENCH DEWATERING WATER, WHICH HAVE CHARACTERISTICS SIMILAR TO STORMWATER RUNOFF AT THE SITE, INTO A CONTROLLED CONVEYANCE SYSTEM BEFORE DISCHARGE TO A SEDIMENT TRAP OR SEDIMENT POND.
- b. PERMITTEES MAY DISCHARGE CLEAN, NON-TURBID DEWATERING WATER, SUCH AS WELL-POINT GROUNDWATER, TO SYSTEMS TRIBUTARY TO, OR DIRECTLY INTO SURFACE WATERS OF THE STATE, AS SPECIFIED IN ELEMENT 8: STABILIZE CHANNELS AND OUTLETS, PROVIDED THE DEWATERING FLOW DOES NOT CAUSE EROSION OR FLOODING OF RECEIVING WATERS. DO NOT ROUTE CLEAN DEWATERING WATER THROUGH STORMWATER SEDIMENT PONDS. NOTE THAT SURFACE WATERS OF THE STATE MAY EXIST ON A CONSTRUCTION SITE AS WELL AS OFF SITE; FOR EXAMPLE, A CREEK RUNNING THROUGH A SITE.
- c. OTHER DEWATERING TREATMENT OR DISPOSAL OPTIONS MAY INCLUDE:
 - i. INFILTRATION
 - ii. TRANSPORT OFF SITE IN A VEHICLE, SUCH AS A VACUUM FLUSH TRUCK, FOR LEGAL DISPOSAL IN A MANNER THAT DOES NOT POLLUTE STATE WATERS.
 - iii. ECOLOGY-APPROVED ON-SITE CHEMICAL TREATMENT OR OTHER SUITABLE TREATMENT TECHNOLOGIES.
 - iv. SANITARY OR COMBINED SEWER DISCHARGE WITH LOCAL SEWER DISTRICT APPROVAL, IF THERE IS NO OTHER OPTION.
 - v. USE OF A SEDIMENTATION BAG WITH DISCHARGE TO A DITCH OR SWALE FOR SMALL VOLUMES OF LOCALIZED DEWATERING.
 - vi. PERMITTEES MUST HANDLE HIGHLY TURBID OR CONTAMINATED DEWATERING WATER SEPARATELY FROM STORMWATER.

ELEMENT 11 – MAINTAIN BMPs

- a. PERMITTEES MUST MAINTAIN AND REPAIR ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL BMPs AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION IN ACCORDANCE WITH BMP SPECIFICATIONS.
- b. PERMITTEES MUST REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPs WITHIN 30 DAYS AFTER ACHIEVING FINAL SITE STABILIZATION OR AFTER THE TEMPORARY BMPs ARE NO LONGER NEEDED.

ELEMENT 12 – MANAGE THE PROJECT

- a. PHASE DEVELOPMENT PROJECTS TO THE MAXIMUM DEGREE PRACTICABLE AND TAKE INTO ACCOUNT SEASONAL WORK LIMITATIONS.
- b. INSPECTION AND MONITORING – INSPECT, MAINTAIN AND REPAIR ALL BMPs AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. PROJECTS REGULATED UNDER THE CONSTRUCTION STORMWATER GENERAL PERMIT (CSWGP) MUST CONDUCT SITE INSPECTIONS AND MONITORING IN ACCORDANCE WITH SPECIAL CONDITION S4 OF THE CSWGP.
- c. MAINTAINING AN UPDATED CONSTRUCTION SWPPP.

ELEMENT 13 – PROTECT LOW IMPACT DEVELOPMENT (LID) BMPs

- a. THE PRIMARY PURPOSE OF LID BMPs/ON-SITE LID STORMWATER MANAGEMENT BMPs IS TO REDUCE THE DISRUPTION OF THE NATURAL SITE HYDROLOGY. LID BMPs ARE PERMANENT FACILITIES.
- b. PERMITTEES MUST PROTECT ALL BIORETENTION AND RAIN GARDEN FACILITIES FROM SEDIMENTATION THROUGH INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL BMPs ON PORTIONS OF THE SITE THAT DRAIN INTO THE BIORETENTION AND/OR RAIN GARDEN FACILITIES. RESTORE THE FACILITIES TO THEIR FULLY FUNCTIONING CONDITION IF THEY ACCUMULATE SEDIMENT DURING CONSTRUCTION. RESTORING THE FACILITY MUST INCLUDE REMOVAL OF SEDIMENT AND ANY SEDIMENT-LADEN BIORETENTION/RAIN GARDEN SOILS, AND REPLACING THE REMOVED SOILS WITH SOILS MEETING THE DESIGN SPECIFICATION.
- c. PERMITTEES MUST MAINTAIN THE INFILTRATION CAPABILITIES OF BIORETENTION AND RAIN GARDEN FACILITIES BY PROTECTING AGAINST COMPACTION BY CONSTRUCTION EQUIPMENT AND FOOT TRAFFIC. PROTECT COMPLETE LAWN AND LANDSCAPED AREAS FROM COMPACTION DUE TO CONSTRUCTION EQUIPMENT.
- d. PERMITTEES MUST CONTROL EROSION AND AVOID INTRODUCING SEDIMENT FROM SURROUNDING LAND USES ONTO PERMEABLE PAVEMENTS. DO NOT ALLOW MUDDY CONSTRUCTION EQUIPMENT ON THE BASE MATERIAL OR PAVEMENT. DO NOT ALLOW SEDIMENT-LADEN RUNOFF ONTO PERMEABLE PAVEMENTS.
- e. PERMITTEES MUST CLEAN PERMEABLE PAVEMENTS FOULED WITH SEDIMENTS OR NO LONGER PASSING AN INITIAL INFILTRATION TEST USING LOCAL STORMWATER MANUAL METHODOLOGY OR THE MANUFACTURER'S PROCEDURES.
- f. PERMITTEES MUST KEEP ALL HEAVY EQUIPMENT OFF EXISTING SOILS UNDER LID FACILITIES THAT HAVE BEEN EXCAVATED TO FINAL GRADE TO RETAIN THE INFILTRATION RATE OF THE SOILS.

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
VAN, WA 98757-5865
(360) 416-4400

DATE	REVISIONS



PROJECT NO. EC27405
DESIGNED BY: R.S.E. / APPROVED BY: R.W.
CHECKED BY: R.S.E. / DRAWN BY: R.S.E.
DESIGNED BY: R.S.E. / APPROVED BY: R.W.
CHECKED BY: R.W. / DRAWN BY: R.W.

PROJECT LOCATED NEAR:
CONCRETE, WA
S 141.34 N 91.8 E


**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**

TESS NOTES & SWPPP ELEMENTS

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
3 OF 30





WSDOT Notes

1. Notify WSDOT CTCO 5 days before starting Work by contacting austin.bighorse@wsdot.wa.gov or (206) 440-4430.
2. At time of Work, call WSDOT Radio at (206) 440-4490 when lane/shoulder is closed, and again when lane/shoulder is opened. Leave contact name and mobile phone number with WSDOT Radio.
3. Notify Transit Agencies & affected businesses 5 days prior to beginning Work. Assistance or signed detour shall be provided.
4. Pedestrians and bicyclists shall be accommodated through the work zone.
5. Only essential equipment and materials shall be on WSDOT R/W during working hours. No equipment or materials shall be on WSDOT R/W during non-working hours.
6. Channelization devices shall be Traffic Safety Drums with Type C Lights OR 4" Retro reflective bands meeting WSDOT Standard Specs.
7. During non-Working hours area shall meet criteria in WSDOT Std Specs. 1-07.23, including, but not limited to, "drop off" protection.
8. All W-Series signs shall be 48"x48" Black on Orange.
9. All R-Series signs shall be Black on White.
10. Flagging Station shall be visible from W20 7A. Add additional W20-7A if needed due to limited sight distance.
11. When side street or cross street falls within the sign sequence, signs shall also be placed on the side streets.
12. Lane/shoulder closure hours for installing signs class A shall be Sunday through Thursday 9:00 PM to 5:00 AM nightly. Road closure days and hours shall be deferred to local agency.

Holiday Impacts:
No closures will be allowed from noon the day prior to a holiday or holiday weekend through noon the day following a holiday or holiday weekend. If it is a holiday weekend when the holiday falls on a Friday, Saturday, Sunday, or Monday.




EXHIBIT " B "
Sheet 2 of 4

GENERAL NOTES

1. SIGN SPACING SHALL BE ADJUSTED TO FIT INTERSECTIONS AND DRIVEWAYS.
2. CONTRACTOR SHALL STAGE WORK TO MINIMIZE DISRUPTION TO LOCAL RESIDENTS & EMERGENCY SERVICES.
3. FOR INSTALLING AND REMOVING SIGNS ALONG SR22 AND ANY OTHER ROUTES WITH NARROW SHOULDERS, USE THE SINGLE LANE CLOSURE DETAIL TOP 1 ON PAGE 7. FOR ALL OTHER ROUTES USE THE SHOULDER CLOSURE DETAIL TOP 10.

CONSTRUCTION NOTES

1. INSTALL SIGN(S) ON 4" X 4" WOOD POST WHERE APPROPRIATE, PER WSDOT STD PLAN G-22.10.
2. INSTALL TYPE 3 BARRICADES AND SIGN(S) PER WSDOT STANDARDS.
3. INSTALL SIGN ON STEEL TRIPOD SECURED WITH SANDBAGS WHERE APPROPRIATE.

LEGEND

- # CONSTRUCTION NOTE
- # SIGN NUMBER
- ▨ WORK ZONE
- ▬ TYPE 3 BARRICADES AS NECESSARY TO BLOCK ROAD
- CLASS "A" CONSTRUCTION SIGN
- ▽ CLASS "B" CONSTRUCTION SIGN
- DIRECTION OF TRAFFIC FLOW
- CHANNELIZATION DEVICE
- PCMS PORTABLE CHANGEABLE MESSAGE SIGN
- ⚑ FLAGGER STATION

APPROVAL EXPIRES 6 MONTHS AFTER DATE SIGNED

ACCEPTED AS NOTED
Christa Stea
1/07/2025
WSDOT TRAFFIC OPERATIONS

Within WSDOT Right-of-Way/Limited Access Only
LOCAL AGENCY shall Also Accept

SCALE:
1" = N/A
1" = N/A

NAVJ 88

DAVID EVANS AND ASSOCIATES INC.

SKAGIT COUNTY PUBLIC WORKS
1800 CONTINENTAL PLACE
MOUNTAIN VIEW, WA 98275-5625
(360) 416-1400




NO.	REVISIONS	DATE

PROJECT NO. E02145
FED AID NO. 46SDRWA 4674650
DESIGNED BY: [] DRAWN BY: []
CHECKED BY: R.W. APPROVED BY: R.W.
PROJECT LOCATED NEAR: CONCRETE, WA
CONCRETE, WA 98134-9196

CONCRETE SAUK VALLEY ROAD FISH PASSAGE PROJECT - SOUTH OSTERMAN CREEK
TEMPORARY TRAFFIC CONTROL PLAN (2 OF 4)

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET **5** OF **30**



WSDOT Notes on Sheet 5 of 30.

GENERAL NOTES

1. SIGN SPACING SHALL BE ADJUSTED TO FIT INTERSECTIONS AND DRIVEWAYS.
2. CONTRACTOR SHALL STAGE WORK TO MINIMIZE DISRUPTION TO LOCAL RESIDENTS & EMERGENCY SERVICES.
3. FOR INSTALLING AND REMOVING SIGNS ALONG SR20 AND ANY OTHER ROUTES WITH NARROW SHOULDERS, USE THE SINGLE LANE CLOSURE DETAIL TOP 1 ON PAGE 7. FOR ALL OTHER ROUTES USE THE SHOULDER CLOSURE DETAIL TOP 10.

CONSTRUCTION NOTES

1. INSTALL SIGN(S) ON 4IN X 4IN WOOD POST WHERE APPROPRIATE, PER WSDOT STD PLAN G-22.10.
2. INSTALL TYPE 3 BARRICADES AND SIGNS PER WSDOT STANDARDS.
3. INSTALL SIGN ON STEEL TRIPOD SECURED WITH SANDBAGS WHERE APPROPRIATE.

LEGEND

- ① CONSTRUCTION NOTE
- # SIGN NUMBER
- ▨ WORK ZONE
- ▬ TYPE 3 BARRICADES AS NECESSARY TO BLOCK ROAD
- CLASS "A" CONSTRUCTION SIGN
- ▽ CLASS "B" CONSTRUCTION SIGN
- DIRECTION OF TRAFFIC FLOW
- CHANNELIZATION DEVICE
- PCMS PORTABLE CHANGIBLE MESSAGE SIGN
- 🚧 FLAGGER STATION

APPROVAL EXPIRES 6 MONTHS AFTER DATE SIGNED

ACCEPTED AS NOTED
Christy Stea
 11/07/2025
WSDOT TRAFFIC OPERATIONS

Within WSDOT Right-of-Way/Limited Access Only
LOCAL AGENCY shall Also Accept



SCALE:
 1" = N/A
 1" = N/A



EXHIBIT " B "
 Sheet 3 of 4

SKAGIT COUNTY PUBLIC WORKS
 1890 CONTINENTAL PLACE
 MOUNT VERNON, WA 98273-5025
 (360) 416-1600

NO.	REVISIONS	DATE




PROJECT NO. 65201145
 FEDERAL AID NO. 4650000001046000 SHEET 3 OF 30 DRAWING B-CIVIL SHEET 1011531_TC_01.DWG

DESIGNED BY: [Signature]
 CHECKED BY: R.W.
 APPROVED BY: R.W.
 PROJECT LOCATED NEAR: CONCRETE, WA
 STATE AGENCY: [Signature]

CONCRETE SAUK VALLEY ROAD
 FISH PASSAGE PROJECT -
 SOUTH OSTERMAN CREEK
 TEMPORARY TRAFFIC CONTROL PLAN (3 OF 4)

1" HORIZONTAL SCALE BAR
 ADJUST SCALE ACCORDINGLY

SHEET
6 OF 30




PROJECT LIMIT
STA. 219+18.75
N.526324.546
E.1454009.140

REFER TO SHEETS 17 AND 27
FOR ALIGNMENT INFORMATION

PROPOSED TEMPORARY CONSTRUCTION EASEMENT ACQUISITION						
PARCEL ID	PARCEL #	PROPERTY OWNER(S)	OWNER MAILING ADDRESS	LOT AREA (SQ FT)	TEMPORARY CONSTRUCTION EASEMENT (SQ FT)	REMAINING AREA (SQ FT)
1	P30970	LORI D. MANNING	17705 67TH AVE E. PUYALLUP, WA 98375	±99,317	±33,394	±65,923
2	P30972	SIERRA PACIFIC LAND & TIMBER CO.	PO BOX 496028, REDDING, CA 96049	±2,592,383	±19,756	±2,572,628

PROJECT LIMIT
STA. 104+00.00
N. 526608.175
E. 1454079.430



PROJECT LIMIT
STA. 100+00
N.526242.861
E.1454214.466


PROJECT LIMIT
STA. 215+71.93
N.526401.299
E.1454329.180

EROSION CONTROL KEYNOTES

1. PRESERVING NATURAL VEGETATION (BMP C101).
2. SITE REVEGETATION SHALL CONFORM TO THE SPECIAL PROVISIONS AND SHEETS 25 & 26
3. MATERIALS DELIVERY, STORAGE & CONTAINMENT (BMP C153)
4. STREET CLEANING (BMP C107)
5. DUST CONTROL (BMP C140)
6. SURFACE ROUGHENING (BMP C130)
7. MAINTAIN ACCESS DURING CONSTRUCTION.
8. SEEDING & MULCHING (BMP C120 & C121). MULCHING SHALL BE "LONG-TERM MULCH" MEETING THE SPECIFICATIONS OF 9-14.5(2)A OF THE STANDARD SPECIFICATIONS.
9. DRIVEWAY LOCATION NOT SURVEYED BY LICENSED SURVEYOR. CONTRACTOR TO FIELD VERIFY LOCATION.

LEGEND

- HIGH VISIBILITY FENCE (BMP C103)
- SAW-CUTTING LIMITS (BMP C152)
- STABILIZED CONSTRUCTION ENTRANCE (C105)
- WATTLES (BMP C235)
- LIMITS OF VEGETATION REMOVAL
- DITCH
- TRIANGULAR SILT DIKE (BMP C208)
- DRAINAGE FLOW DIRECTION ARROWS (SHEET FLOW, OR SHALLOW CHANNEL FLOW) ON ROADWAY
- DRAINAGE FLOW DIRECTION ARROWS (SHEET FLOW, OR SHALLOW CHANNEL FLOW) OFF ROADWAY.



NOTE: FOR FILL CONDITIONS 4.
FOR CUT CONDITIONS 4 TO 9

**DETAIL "A" HVF
INSTALLATION (TYP)**
N.T.S




SCALE:
1" = 20' HOR
1" = N/A



**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
SEASIDE, WA 98274-9625
(360) 416-4400

NO.	REVISIONS	DATE



PROJECT NO. EC07045
DES. AND DRS. ABBEY/DAVID EVANS
DESIGNED BY: R.S.E.
CHECKED BY: T.M.W.
APPROVED BY: T.M.W.

PROJECT LOCATED NEAR:
CONCRETE, WA
S 141.341 N 9 E


**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**

TESS PLAN

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

J:\E - September 29, 2025 - 12:49 PM - P:\SKAGIT\00000131040\CAD\SHETS\0000 CAD-2025\10 DRAWING\B-CIVIL SHEET\201702_EC_BO.DWG


NO.	REVISIONS	DATE



COUNTY ENGINEER


PROJECT NO. EC02145	DESIGNED BY: NT	CHECKED BY:	PROJECT LOCATED NEAR: CONCRETE, WA S 141.34 N 19 E
TED AND ASSOCIATES INC. 46600000000000000000	DRAWN BY: DCS	APPROVED BY:	

**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**
SITE ISOLATION & DEWATERING DETAILS




- NOTES:**
1. STREAM BYPASS INTAKE SHALL REST ON EXISTING STREAMBED.
 2. PUMP INTAKE SHALL BE FITTED WITH FISH SCREEN MEETING APPLICABLE RCW SECTIONS (RCW 77.57.010 AND 77.57.070), AS WELL AS NMFS CRITERIA. SEE SECTION 7-06 FOR MORE INFORMATION.
 3. PUMP CAPACITY SHALL BE SIZED TO CONVEY THE ENTIRETY OF STREAMFLOW WITHOUT DEWATERING THE CHANNEL OUTSIDE THE ISOLATED WORK AREA. VARIABLE PUMPING MAY BE REQUIRED. SEE PROJECT PERMITS AND SECTION 8-31 FOR MORE INFORMATION.

BYPASS PUMP INTAKE (1/11)
NOT TO SCALE




- NOTES:**
1. CORRUGATED PLASTIC OR METAL PIPE 36" MIN DIAMETER PERFORATED PIPE, ONE PER EACH PUMP.
 2. STREAMBED SEDIMENT.
 3. LIMIT OF EXCAVATION. INSTALL PIPE AND BACKFILL WITH STREAMBED SEDIMENT.
 4. PUMP INTAKE SHALL BE FITTED WITH FISH SCREEN MEETING RCW 77.57.010 AND RCW 77.57.070.
 5. THE INTENT OF DEWATERING PUMPS IS TO REMOVE GROUNDWATER OR SURFACE WATER WHICH SEEPS INTO THE ISOLATED WORK AREA. DEWATERING PUMPS ARE OPTIONAL; IF USED, DEWATERING PUMPS SHALL BE OPERATED IN SUCH A WAY THAT NO PORTION OF THE STREAMBED OUTSIDE THE ISOLATED WORK AREA BECOMES DEWATERED.
 6. THE DEWATERING PUMP INTAKE SHOWN ON THIS SHEET IS ONE EXAMPLE OF AN ELEMENT TO BE INCLUDED IN THE DEWATERING PLAN; ADDITIONAL ELEMENTS MAY BE REQUIRED TO DEWATER THE SITE AS REQUIRED IN THE SPECIAL PROVISIONS.
 7. DIVERSION OF SURFACE FLOWS AND ALL DEWATERING SHALL BE CLOSELY COORDINATED AND TIMED WITH FISH EXCLUSION EFFORTS. DIVERSION OF SURFACE FLOWS AND/OR DEWATERING SHALL NOT OCCUR UNTIL FISH EXCLUSION EFFORTS HAVE BEEN COMPLETED.


DEWATERING PUMP INTAKE (2/11)
NOT TO SCALE



ENERGY DISSIPATOR (3/11)
NOT TO SCALE





COFFERDAM (4/11)
NOT TO SCALE



SECTION A-A

NI - September 25, 2025 - 2:38 PM - P:\A\DAVID EVANS AND ASSOCIATES\SOUTH_OSTERMAN_CONSTRUCTION_SUPPORT_DEA-17\DESIGN\CAD DWG\TSC DETAIL3.DWG



GENERAL SHEET NOTES


- FOR CREEK DESIGN, SEE STREAM DRAWINGS ON SHEETS 17-26.
- FOR ROAD SUPERELEVATION DIAGRAM, SEE SHEET 15.
- REFER TO FINAL GEOTECH REPORT DATED 10/11/2021 FOR COMPACTION & MATERIAL REQUIREMENTS.

CONSTRUCTION NOTES

- PRECAST REINF. CONC. SPLIT BOX CULVERT NO. 1S, SEE CULVERT SHEETS FOR DESIGN DETAILS.
- PAVING LIMITS. MATCH EXIST GRADE & SEAL ALL BUTT JOINTS, SEE DETAIL E ON SHEET 13.
- INSTALL PAINTED YELLOW DOUBLE CENTERLINE PER WSDOT STD PLAN M-20.10.
- INSTALL PAINTED WHITE EDGE LINE PER WSDOT STD PLAN M-20.10.
- INSTALL BEAM GUARDRAIL TYPE 31 PER WSDOT STD PLAN C-20.10.
- INSTALL BEAM GUARDRAIL TYPE 31 NON-FLARED TERMINAL PER WSDOT STD PLAN C-22.40-11.
- INSTALL BEAM GUARDRAIL TYPE 31 W/ BOX CULVERT GUARDRAIL STEEL POST TYPE 31 PER WSDOT STD PLAN C-20.41.
- INSTALL BEAM GUARDRAIL ANCHOR TYPE 11 TERMINAL PER WSDOT STD PLAN C-23.70-01.
- INSTALL BEAM GUARDRAIL PLACEMENT STRONG POST TYPE 31 PER WSDOT STD PLAN C-20.44.

LEGEND

- DITCH
- LIMITS OF HMA CL 1/2 IN. PG 58H-22 SURFACING
- LIMITS OF GRAVEL SHOULDER SURFACING



SCALE:
 1" = 20' HOR
 1" = 20' VER

NAVD 88



SKAGIT COUNTY PUBLIC WORKS
 1800 CONTINENTAL PLACE
 BELLINGHAM, WA 98275-5625
 (360) 416-4400

NO.	REVISIONS	DATE


CONCRETE SAUK VALLEY ROAD FISH PASSAGE PROJECT - SOUTH OSTERMAN CREEK
 ROAD PLAN & PROFILE

PROJECT NO. 16C0745
 DESIGNED BY: R.S.E. (RSE)
 CHECKED BY: R.W. (RWB)
 PROJECT LOCATED NEAR: CONCRETE, WA
 S 141.341918 E

1 INCH SCALE BAR
 ADJUST SCALE ACCORDINGLY


SHEET
12 OF 30

J:\E - October 17, 2025 - 12:44 PM - P:\S\SKAG\0000031\0400\CAD\SHEET\5030 CAD-2025\010 DRAWING\B-C\ML SHEET\201702L_PP_50.DWG




SUPERELEVATION DIAGRAM - CONCRETE SAUK VALLEY ROAD


SCALE:
 1" = 20' HOR
 1" = 4' VER




A ROADWAY SECTION FOR STABILIZED CONSTRUCTION ENTRANCE
 Scale: 1" = 4'




B ROAD TYPICAL SECTION FOR CONCRETE SAUK VALLEY RD (STA. 100+75.00 TO STA. 102+95.00)
 Scale: 1" = 4'
 ** REFER TO SUPERELEVATION DIAGRAM ABOVE



C ROAD TYPICAL SECTION FOR CONCRETE SAUK VALLEY RD (STA. 100+00.00 TO STA. 100+75.00)
 Scale: 1" = 4'
 ** REFER TO SUPERELEVATION DIAGRAM ABOVE



D ROAD TYPICAL SECTION FOR CONCRETE SAUK VALLEY RD (STA. 102+95.00 TO STA. 104+00.00)
 Scale: 1" = 4'
 ** REFER TO SUPERELEVATION DIAGRAM ABOVE



E LONGITUDINAL BUTT-JOINT PLANING DETAIL
 NTS



SKAGIT COUNTY PUBLIC WORKS
 1800 CONTINENTAL PLACE
 BURLINGAME, WA 98075-9625
 (360) 416-4400

NO.	REVISIONS	DATE




PROJECT NO. ECR2045
 DESIGNED BY: ABE/DAV/AR/ABG
 DRAWN BY: R.S.E.
 CHECKED BY: R.W.
 APPROVED BY: R.W.
 PROJECT LOCATED NEAR:
 CONCRETE, WA
 S 141.341N19E

PROJECT NO.	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
ECR2045	ABE/DAV/AR/ABG	R.S.E.	R.W.	R.W.

**CONCRETE SAUK VALLEY ROAD
 CULVERT REPAIR PROJECT -
 SOUTH OSTERMAN CREEK**
 SUPERELEVATION DIAGRAM & TYPICAL
 SECTIONS

1" INCH SCALE BAR
 ADJUST SCALE ACCORDINGLY

J:\E - September 29, 2025 - 12:50 PM - P:\SKAGIT\0000011040\CAD\SHETS\000 CAD-2025\10 DRAWING\B-CIVL SHEET\01702L_PP_80.DWG



SCALE:
 1" = 10' HOR
 1" = 10' VER



SKAGIT COUNTY
PUBLIC WORKS
 1800 CONTINENTAL PLACE
 BELLINGHAM, WA 98275-9625
 (360) 416-4400

NO.	REVISIONS	DATE



EXEMPTED RECORD

PROJECT NO. 16C7145	DESIGNED BY: R.S.E.	DRAWN BY: R.S.E.
REV. AND NO. AS SHOWN ON DRAWING	CHECKED BY: R.W.	APPROVED BY: R.W.
PROJECT LOCATED NEAR: CONCRETE, WA S 14 T 34 N R 9 E		


**CONCRETE SAUK VALLEY ROAD
 CULVERT REPAIR PROJECT -
 SOUTH OSTERMAN CREEK**
 ROAD X-SECTIONS

1 INCH SCALE BAR
 ADJUST SCALE ACCORDINGLY

J:\E - September 29, 2025 - 12:50 PM - P:\SKAGIT\00000110400\CAD\SHETS\000 CAD-2025\10 DRAWING\GR-CIVL SHEET\201702L_PP_60.DWG

STRUCTURAL NOTES

1. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF WSDOT'S MOST CURRENT EDITION OF "STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION."
2. THE CULVERTS SHALL BE DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF AASHTO'S LRFD BRIDGE DESIGN SPECIFICATIONS 10TH EDITION 2024.
3. THE SEISMIC PEAK GROUND ACCELERATION OF 0.26 AND SITE CLASS E SHALL BE USED FOR THE SEISMIC DESIGN.
4. LIVE LOAD (LL) AASHTO HL-93 + IM AS SHOWN.
5. THE PRECAST CONCRETE SHALL BE CLASS 5000, 6000 OR 7000 SELF CONSOLIDATING CONCRETE (SCC), OTHER CONCRETE SHALL BE CLASS 4000.
6. STEEL REINFORCING SHALL CONFORM TO ASTM A615 GRADE 60.
7. SEGMENTAL PRECAST CONCRETE BOX CULVERT UNITS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE ASTM C 785 AND WSDOT STANDARD SPECIFICATION SECTION 6-02.3(20). ALL JOINTS SHALL BE TONGUE AND GROOVE AND SEALED WITH JOINT SEALANT PER ASTM C990 AND WRAPPED WITH EXTERNAL SEALING BAND PER ASTM C877.
8. ALL STEEL PLATES AND SHAPES SHALL BE ASTM A36 OR ASTM A 992. ALL BOLTS, NUTS AN WASHERS (UNLESS NOTED OTHERWISE) SHALL BE ASTM A 307 AND COMPLY WITH WSDOT STANDARD SPECIFICATION 9-16.3(4) AND RESIN BONDED ANCHORS SHALL BE ASTM A 193 GRADE B7, OR ASTM A449. ALL STEEL PLATES SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M111 AFTER FABRICATION. BOLTS AND HARDWARE SHALL BE GALVANIZED IN ACCORDANCE WITH ASHTO M 232.
9. UNLESS OTHERWISE SHOWN IN THE PLANS, CONCRETE COVER MEASURED FROM THE FACE OF CONCRETE TO THE FACE OF ANY REINFORCING STEEL SHALL BE 2" AT THE TOP OF THE ROOF DECK, 1½" AT THE BOTTOM OF THE ROOF DECK, 3" AT THE BOTTOM OF FOOTINGS, AND 2" AT ALL OTHER LOCATIONS.
10. THE BACKFILL AT BOTH SIDES OF THE CULVERT TO BE PLACED IN ACCORDANCE TO WSDOT STANDARD SPECIFICATION 2-09.3(1).E. THE MAXIMUM FIELD HEIGHT DIFFERENCE MEASURED FROM SIDE TO SIDE SHALL BE NO MORE 2'-0". THE MAXIMUM FIELD HEIGHT DIFFERENCE MEASURED FROM SIDE TO SIDE SHALL NOT BE MORE THAN 2'-0".
11. A FOUNDATION MATERIAL LAYER SHALL BE PLACED CONSISTING OF A MINIMUM OF 12 INCHES CRUSHED ROCK PRODUCT OR PERMEABLE BALLAST PER WSDOT STANDARD SPECIFICATION 9.03.9(2) AND CONFORMING TO THE REQUIREMENTS OF THE GEOTECHNICAL REPORT.
12. ADDITIONAL OVER-EXCAVATION OF 1 TO 2 FEET MAY BE REQUIRED TO PROPERLY SUPPORT THE PLANNED STRUCTURES IF EXCESSIVELY SOFT, ORGANIC, OR OTHERWISE UNSUITABLE SOILS ARE ENCOUNTERED AT THE SUBGRADE ELEVATION.
13. CONTRACTOR MAY ENCOUNTER GROUNDWATER DURING CULVERT EXCAVATION OF AND SHALL PROVIDE DEWATERING OF EXCAVATIONS AND PROPERLY DISPOSE OF THIS WATER PER THE SPECIAL PROVISIONS.
14. ALL GEOTECHNICAL RECOMMENDATIONS ARE INCLUDED IN THE REPORT BY GEOENGINEERS DATED 10/11/2021 MADE PART OF THESE CONTRACT DOCUMENTS.



**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
EVERETT, WA 98273-9625
(800) 416-1400

NO.	REVISIONS	DATE




PROJECT NO. EC21045
DESIGNED BY: J.M.W.
CHECKED BY: T.M.W.
APPROVED BY: T.M.W.
PROJECT LOCATED NEAR:
CONCRETE, WA
S 14 T 34 N R 8 E

CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK


STRUCTURAL NOTES

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY






CULVERT PLAN



CULVERT ELEVATION
LOOKING AHEAD ON STATION




TYPICAL SECTION

GENERAL SHEET NOTES

- CABLE FENCE MOUNTED ON TOP OF ALL HEADWALLS AND WING WALLS TO BE CONSTRUCTED PER WSDOT STANDARD DETAILS 8.1-A6-2, 8.1-A6-3, 8.1-A6-4, & 8.1-A6-5.

LEGEND

- INDEX CONTOUR
- INTERMEDIATE CONTOUR
- PRECAST WINGWALL
- PERMEABLE BALLAST
- UNSATURABLE FOUNDATION EXCAVATION INCL. HAUL



SCALE:
1" = 5' HOR
1" = N/A



NAVJ 88

SKAGIT COUNTY
PUBLIC WORKS
1800 CONTINENTAL PLACE
EVERETT, WA 98273-5625
(800) 416-4400

NO.	REVISIONS	DATE




PROJECT NO. 16C7045
DES. AND NO. A6030AW-16-1668
DESIGNED BY P.S.S.
CHECKED BY T.M.W.
APPROVED BY T.M.W.
PROJECT LOCATED NEAR:
CONCRETE, WA
S 14 T 34 N R 9 E


CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK
CULVERT PLAN & ELEVATION

1" INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
16 OF 30



WINGWALL LAYOUT
LOOKING AHEAD ON STATION



WINGWALL LAYOUT
LOOKING BACK ON STATION



DAVID EVANS
AND ASSOCIATES INC.

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
BELLINGHAM, WA 98275-8625
(360) 416-4400

NO.	REVISIONS	DATE




EXAMINEE OF RECORD

PROJECT NO. 1607045	DESIGNER'S P.S.S. APPROVED FOR RECORD
DESIGNED BY T.M.W.	DRAWN BY D.J.L.
CHECKED BY T.M.W.	APPROVED BY T.M.W.
PROJECT LOCATED NEAR: CONCRETE, WA S 14 T 34 N R 8 E	


**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**
CULVERT WINGWALL LAYOUTS

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY


SHEET
17 OF 30




PLAN - SOUTH OSTERMAN CREEK CULVERT (WEST)



PLAN - SOUTH OSTERMAN CREEK CULVERT (EAST)



VIEW A - SOUTH OSTERMAN CREEK CULVERT (WEST)



VIEW B - SOUTH OSTERMAN CREEK CULVERT (EAST)

SKAGIT COUNTY
PUBLIC WORKS
1800 CONTINENTAL PLACE
BOSTON, WA 98273-9625
(360) 416-4400

NO.	REVISIONS	DATE




PROJECT NO. 1607045
DESIGNED BY: J.S.S.
CHECKED BY: T.M.W.
APPROVED BY: T.M.W.
PROJECT LOCATED NEAR:
CONCRETE, WA
S 14 T 34 N R 8 E

CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK
CULVERT HEADWALL LAYOUTS

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY



J:\E - September 29, 2025 - 12:56 PM - P:\SKAGIT\0000000110400\CAD\SHETS\000 CAD-2025\010 DRAWING\G-STRUCTURAL SHEET\01100_CULV_DET_S0.DWG




T1 STRUCTURE ID (SEE SHEET 26 FOR STAKEOUT)

CHANNEL PLAN

NOTES:


1. CHANNEL PLAN PRESENTED ON THIS SHEET REPRESENTS NEATLINE ELEVATIONS FOR CONSTRUCTION, ACTUAL FINISH GRADE WILL INCLUDE SIGNIFICANT VARIABILITY DUE TO LOGS, RACKING, AND STREAMBED BOULDERS AND COBBLES.
2. SEE SHEET 21 FOR TYPICAL CHANNEL SECTIONS AND STREAMBED MIX.
3. SEE SHEETS 26 THROUGH 28 FOR CHANNEL STRUCTURE DETAILS.
4. LOCATION OF DRIVEWAY IS APPROXIMATE. STAKEOUT AND APPROVAL OF GRADING LIMITS AND TIMBER HANDRAIL LOCATION IS REQUIRED PRIOR TO STARTING WORK.



Natural Systems Design
+ Coastal Geologic Services

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
SEASIDE, WA 98274-8625
(360) 416-1400

NO.	REVISIONS	DATE



PROJECT NO. EC20245
DES. AND DRS. ARS/DAVID/AR/AGB
DESIGNED BY: NT
CHECKED BY: NT
DRAWN BY: DES
APPROVED BY: NT
PROJECT LOCATED NEAR:
CONCRETE, WA
S 147.34 N R 8 E

CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK

CHANNEL PLAN

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
19 OF 30


NO.	REVISIONS	DATE



COUNTY ENGINEER

PROJECT NO. 15020000	DESIGNED BY: JNT	DRAWN BY: DES	APPROVED BY: [Signature]
FILED NO. 15020000	CHECKED BY: [Signature]	PROJECT LOCATED NEAR: CONCRETE, WA	E 88 N 141 S 141 S

**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**
CHANNEL PROFILE



CHANNEL LINE PROFILE

SCALE: 1"=20' HORIZ., 1"=4' VERT.


NOTES:

- CHANNEL PROFILE PRESENTED ON THIS SHEET REPRESENT NEATLINE ELEVATIONS FOR CONSTRUCTION. ACTUAL FINISH GRADE WILL INCLUDE SIGNIFICANT VARIABILITY DUE TO LOGS, RACKING, AND STREAMBED BOULDERS AND COBBLES.
- SEE SHEET 21 FOR TYPICAL CHANNEL SECTIONS AND STREAMBED MIX.
- SEE SHEETS 26 THROUGH 28 FOR CHANNEL STRUCTURE DETAILS.



Natural Systems Design
+ Coastal Geologic Services


STATION	CHANNEL STAKEOUT																			
	DAYLIGHT			LEFT			TOB			€			TOE			RIGHT				
	OFFSET	ELEV.	C/F	OFFSET	ELEV.	OFFSET	ELEV.	OFFSET	ELEV.	OFFSET	ELEV.	OFFSET	ELEV.	OFFSET	ELEV.	OFFSET	ELEV.	C/F		
219+81.8	10.7 L	293.2	CUT	10.5 L	293.1	8.5 L	293.1	7.0 L	292.1	0.0	291.4	7.0 R	292.1	8.5 R	293.1	10.5 R	293.1	12.4 R	293.1	FILL
219+75	11.3 L	293.2	CUT	10.5 L	292.8	8.5 L	292.8	7.0 L	291.8	0.0	291.1	7.0 R	291.8	8.5 R	292.8	10.5 R	292.8	11.6 R	292.8	FILL
219+50	14.1 L	293.3	CUT	10.5 L	291.5	8.5 L	291.5	7.0 L	290.5	0.0	289.8	7.0 R	290.5	8.5 R	291.5	10.5 R	292.5	10.6 R	292.6	CUT
219+25	20.8 R	296.4	CUT	10.5 L	291.3	8.5 L	290.3	7.0 L	289.3	0.0	288.6	7.0 R	289.3	8.5 R	290.3	10.5 R	291.3	12.1 R	292.1	CUT
219+00	26.3 R	298.0	CUT	10.5 L	290.0	8.5 L	289.0	7.0 L	288.0	0.0	287.3	7.0 R	288.0	8.5 R	289.0	10.5 R	290.0	13.7 R	290.0	FILL
218+75	25.9 L	296.5	CUT	10.5 L	288.8	8.5 L	287.8	7.0 L	286.8	0.0	286.1	7.0 R	286.8	8.5 R	287.8	10.5 R	288.8	12.4 R	289.7	FILL
CULVERT 0+00				10.5 L	288.3	7.7 L	287.0	6.2 L	286.0	1.0	285.4	8.5 R	286.3	10.1 R	287.3	10.5 R	287.5			
218+50				10.5 L	286.7	8.5 L	286.5	7.0 L	285.5	0.0	284.8	7.0 R	285.5	8.5 R	286.5	10.5 R	286.7			
218+25				10.5 L	285.5	8.5 L	285.3	7.0 L	284.3	0.0	283.6	7.0 R	284.3	8.5 R	285.3	10.5 R	285.5			
218+17.2				10.5 L	285.1	8.5 L	284.9	7.0 L	283.9	0.0	283.2	7.0 R	283.9	8.5 R	284.9	10.5 R	285.1			
218+00	30.3 L	287.1	FILL	13.7 L	284.6	11.7 L	284.2	9.0 L	283.2	0.0	282.3	11.4 R	283.4	12.9 R	284.5	14.9 R	285.5	25.4 R	290.8	CUT
217+88	34.2 L	286.5	FILL	17.9 L	284.1	15.9 L	283.7	13.3 L	282.6	0.0	281.7	14.8 R	282.8	16.7 R	284.0	18.7 R	285.0	22.8 R	287.0	CUT
217+75	20.0 L	284.0	FILL	19.5 L	283.7	17.5 L	283.3	15.0 L	282.1	0.0	281.1	15.0 R	282.1	17.5 R	283.3	19.5 R	283.5	25.1 R	284.1	FILL
217+60	21.3 L	284.5	CUT	19.5 L	283.6	17.5 L	282.6	15.0 L	281.3	0.0	280.3	15.0 R	281.3	17.5 R	282.6	19.5 R	282.8	36.5 R	284.0	FILL
217+50	22.4 L	284.5	CUT	19.5 L	283.1	17.5 L	282.1	15.0 L	280.8	0.0	279.8	15.0 R	280.8	17.5 R	282.1	19.5 R	282.3	21.2 R	283.9	CUT
217+38.8	25.8 L	285.7	CUT	19.5 L	282.5	17.5 L	281.5	15.0 L	280.3	0.0	279.3	15.0 R	280.3	17.5 R	281.5	19.5 R	282.5	24.0 R	284.8	CUT
217+25	28.5 L	286.8	CUT	19.5 L	282.3	17.5 L	281.3	15.0 L	280.0	0.0	279.0	15.0 R	280.0	17.5 R	281.3	19.5 R	282.3	23.9 R	284.5	CUT
217+15	29.3 L	287.0	CUT	19.5 L	282.1	17.5 L	281.1	15.0 L	279.8	0.0	278.8	15.0 R	279.8	17.5 R	281.1	19.5 R	282.1	23.8 R	284.2	CUT
217+00	46.1 L	295.1	CUT	19.5 L	281.8	17.5 L	280.8	15.0 L	279.5	0.0	278.5	15.0 R	279.5	17.5 R	280.8	19.5 R	281.8	23.9 R	283.9	CUT
216+75	42.6 L	292.8	CUT	19.5 L	281.3	17.5 L	280.3	15.0 L	279.0	0.0	278.0	15.0 R	279.0	17.5 R	280.3	19.5 R	281.3	25.2 R	284.1	CUT
216+50	29.0 L	285.5	CUT	19.5 L	280.8	17.5 L	279.8	15.0 L	278.5	0.0	277.5	15.0 R	278.5	17.5 R	279.8	19.5 R	280.8	23.4 R	282.7	CUT
216+25	41.4 L	291.2	CUT	19.5 L	280.3	17.5 L	279.3	15.0 L	278.0	0.0	277.0	15.0 R	278.0	17.5 R	279.3	19.5 R	280.3	23.7 R	282.4	CUT
216+00	25.7 L	282.9	CUT	19.5 L	279.8	17.5 L	278.8	15.0 L	277.5	0.0	276.5	15.0 R	277.5	17.5 R	278.8	19.5 R	279.8	21.5 R	280.8	CUT
215+92.4	23.7 L	281.7	CUT	19.5 L	279.6	17.5 L	278.6	15.0 L	277.4	0.0	276.4	15.0 R	277.4	17.5 R	278.6	19.5 R	279.6	25.4 R	280.5	FILL



UPSTREAM CHANNEL SECTION
STA 219+82 TO 218+61
SCALE 1" = 5'


STREAMBED MIX	
PERCENT PASSING	PARTICLE SIZE (IN)
100	48
84	26-30
50	7-11
16	0.75-1.5
10	0.25-0.5
5 MIN.	NO. 200 SIEVE

STREAMBED MIX DEPTH	
STATION RANGE	DEPTH
219+82 TO 218+61	4'-0"
218+61 TO 218+17	4'-0" MIN.
218+17 TO 217+39	4'-0"
217+39 TO 215+92	6'-0"
215+92 TO 215+75	¾% MIX TO 4'-0" DEPTH




CULVERT SECTION
STA 218+61 TO 218+17
SCALE 1" = 5'

- NOTES:
- SLASH MATERIAL SHALL BE INCORPORATED INTO STREAMBED MIX DURING CHANNEL CONSTRUCTION. SLASH MATERIAL SHALL BE APPROXIMATELY 5-10% OF THE CONSTRUCTED STREAMBED MIX BY VOLUME.
 - PLACE STREAMBED MIX IN LIFTS OF NO MORE THAN 2 FEET. SEAL EACH LIFT BY WASHING IN FINE MATERIALS AND STREAMBED SAND, REFER TO SECTION 8-30 OF THE SPECIAL PROVISIONS.
 - INDIVIDUAL PARTICLES GREATER THAN APPROXIMATELY 24 INCHES SHALL BE USED PRIMARILY TO FORM CHANNEL BANKS; PLACE AS DIRECTED BY THE ENGINEER.
 - SECTION VIEWS AND STAKEOUT ARE ORIENTED LOOKING DOWNSTREAM IN THE CHANNEL AND DOWN-STATION RELATIVE TO THE ALIGNMENT.
 - WOOD NOT SHOWN FOR CLARITY.



DOWNSTREAM CHANNEL SECTION
STA 218+17 TO 215+89
SCALE 1" = 5'

CHANNEL STAKEOUT POINTS	
THWG	LOWEST POINT OF CHANNEL SECTION, ON CENTERLINE
TOE	TOE OF CHANNEL BANK
TOB	TOP OF CHANNEL BANK
MIX	LIMIT OF STREAMBED MIX PLACEMENT
DAYLIGHT (CUT/FILL)	LIMIT OF EXCAVATION OR FILL PLACEMENT



SKAGIT COUNTY PUBLIC WORKS

1800 CONTINENTAL PLACE
SEASIDE, WA 98273-6625
(360) 416-4400

DATE	REVISIONS	NO.

COUNTY ENGINEER

PROJECT NO. EC0245
DESIGNED BY: ARS/DAVID EVANS
DRAWN BY: DES
CHECKED BY: NT
APPROVED BY: [Signature]




PROJECT LOCATED NEAR:
CONCRETE, WA
S 141.34 N 91.8 E




**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**


TYPICAL CHANNEL SECTIONS

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
21 OF 30



- NOTES
- ALL SECTION VIEWS ARE ORIENTED LOOKING DOWNSTREAM IN THE CHANNEL AND DOWN-STATION RELATIVE TO THE ALIGNMENT.
 - WOOD NOT SHOWN FOR CLARITY.
-  EXCAVATION
 -  NATIVE FILL
 -  STREAMBED MIX



Natural Systems Design
+ Coastal Geologic Services

**SKAGIT COUNTY
PUBLIC WORKS**

1800 CONTINENTAL PLACE
EVERETT, WA 98203
(360) 416-1400

NO.	REVISIONS	DATE



COUNTY ENGINEER

PROJECT NO. EC02145	DESIGNED BY: NT	DRAWN BY: DES
FED. AID NO. 865004W-1468	CHECKED BY:	APPROVED BY:
PROJECT LOCATED NEAR: CONCRETE, WA S 14 T 34 N R 8 E		

**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**


CHANNEL SECTIONS (1 OF 3)

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
22 OF 30


NOTES

1. THE CHANNEL CONSTRUCTION SEQUENCE SHOWN ON THIS SHEET IS A RECOMMENDATION ONLY. ALTERNATE SEQUENCES ARE ACCEPTABLE PROVIDED ALL PROJECT ELEMENTS SHOWN ON THESE PLANS AS DESCRIBED IN THE SPECIAL PROVISIONS.




STEP 1

1. EXCAVATE CHANNEL TO STREAMBED FOUNDATION.
2. PLACE FIVE (5) LONG CHANNEL ROOTWADS AND SIX (6) SHORT CHANNEL ROOTWADS.




STEP 2

1. PLACE APPROXIMATELY 40 TYPE 3 AND TYPE 4 STREAMBED BOULDERS ON STREAMBED FOUNDATION AS DIRECTED BY ENGINEER.




STEP 3

1. PLACE 2' LIFT OF STREAMBED MIX IN CHANNEL, INCORPORATING SLASH MATERIAL.
2. SEAL LIFT BY WASHING IN STREAMBED SAND.




STEP 4

1. INSTALL TWO (2) BANK ROOTWADS.
2. PLACE ONE (1) SHORT CHANNEL ROOTWAD.
3. PLACE 2' LIFT OF STREAMBED MIX ALONG FULL LENGTH OF CHANNEL BED, INCORPORATING SLASH MATERIAL.
4. SEAL LIFT BY WASHING IN STREAMBED SAND.



STEP 5

1. CONSTRUCT LOG TRIANGLES PER DETAIL ON SHEET 26 (RACKING MATERIAL, PILES, AND BOULDER COLLARS NOT SHOWN FOR CLARITY).
2. INSTALL TWO (2) SHORT CHANNEL ROOTWADS.



STEP 6

1. PLACE FINAL LIFT OF STREAMBED MIX, INCORPORATING SLASH MATERIAL, TO MEET FINISH GRADE.
2. SEAL FINAL LIFT BY WASHING IN STREAMBED SAND.
3. INSTALL REMAINING SLASH WATTLES AND BANK ROOTWADS (NOT SHOWN FOR CLARITY) AS REQUIRED IN PLANS.

CHANNEL CONSTRUCTION SEQUENCE

SKAGIT COUNTY
PUBLIC WORKS
 1800 CONTINENTAL PLACE
 BELLINGHAM, WA 98275-8625
 (360) 416-1400

NO.	REVISIONS	DATE




COUNTY ENGINEER

PROJECT NO. EC02145	DESIGNED BY: NT	DRAWN BY: DES
FED. AID NO. 465024W-14680	CHECKED BY:	APPROVED BY:
PROJECT LOCATED NEAR: CONCRETE, WA S 141734 N 198 E		


CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK
 CHANNEL CONSTRUCTION SEQUENCE

1 INCH SCALE BAR
 ADJUST SCALE ACCORDINGLY

NOTE: FOR CLARITY, STREAMBED MIX NOT SHOWN IN PLAN VIEW.



LOG TRIANGLE PLAN
SCALE: 1" = 5'




LOG TRIANGLE - ISOMETRIC
NTS


ID NO.	LOGS	STAKEOUT	STATION	OFFSET	ELEVATION
T1	3 X 18" DIA. 35' LONG	A	217+95.2	13.1 R	283.7
		B	217+75.0	12.4 R	282.3
		C	217+85.9	10.1 L	282.4
T2	2 X 18" DIA. 35' LONG 1 X 18" DIA. 40' LONG	A	217+74.0	14.8 L	282.6
		B	217+42.3	13.1 L	281.1
		C	217+62.3	7.1 R	281.3
T3	3 X 18" DIA. 35' LONG	A	217+54.4	15.2 R	281.9
		B	217+24.6	13.3 R	280.5
		C	217+42.4	5.8 L	280.7
T4	3 X 18" DIA. 35' LONG	A	217+27.6	16.0 L	280.6
		B	217+08.4	14.5 L	280.1
		C	217+19.7	7.6 R	279.8

CROSS CHAIN LASHING (TYP)


NOTE: FOR CLARITY, RACKING MATERIALS NOT SHOWN IN SECTION VIEWS.



SECTION A-A
SCALE: 1" = 5'



SECTION B-B
SCALE: 1" = 5'



SECTION C-C
SCALE: 1" = 5'

LOG TRIANGLE NOTES

- LOG TRIANGLE STRUCTURES SHALL BE CONSTRUCTED OF THREE 18" DIA. LOGS WITH INTACT ROOTWADS. SEE TABLE BELOW FOR LOG LENGTH.
- MEMBER LOGS SHALL BE JOINED BY CROSS CHAIN LASHING AT OVERLAPPING CORNERS. SEE DETAIL SHEET 26.
- STRUCTURES SHALL BE CONSTRUCTED TO MATCH STAKEOUT LOCATIONS AND ELEVATIONS AT TOP OF CROSSING LOGS, AS INDICATED ON TABLE.
- DRIVE TWO 14" DIA. 25' LONG (PE-25) VERTICAL PILES AS SHOWN.
- RACKING MATERIAL (4-10" DIA. X 10-30" LOGS) AND SLASH MATERIAL SHALL BE INTERTWINED WITH LOGS AS STRUCTURES ARE ASSEMBLED. PLACE 15-20 PIECES OF RACKING AND 5 CY OF SLASH PER TRIANGLE. RACKING MATERIAL SHALL BE COVERED AND VOIDS FILLED WITH STREAMBED MIX TO NEATLINES SHOWN ON THESE PLANS.
- INSTALL ROCK COLLAR WITH TWO TYPE 4 STREAMBED BOULDERS AT EACH CORNER OF STRUCTURE. SEE DETAIL ON SHEET 27.
- ROCK COLLARS SHALL BE PLACED SUCH THAT THE CONNECTING CHAIN IS TIGHT AND IN CONTACT WITH LOGS FORMING TRIANGLES. CONTRACTOR SHALL COUNTERSINK BOULDERS AS NECESSARY TO ACHIEVE INSTALLATION IN THIS MANNER.

ID NO.	LOGS	STAKEOUT	STATION	OFFSET	ELEVATION
T5	3 X 18" DIA. 35' LONG	A	217+00.0	16.0 L	280.0
		B	216+80.7	14.4 L	279.5
		C	216+92.1	7.6 R	279.2
T6	3 X 18" DIA. 35' LONG	A	216+82.0	14.2 R	279.3
		B	216+53.0	12.6 R	278.8
		C	216+68.1	7.4 L	278.5
T7	3 X 18" DIA. 35' LONG	A	216+58.6	15.3 L	279.1
		B	216+36.4	14.8 L	278.6
		C	216+47.7	7.2 R	278.3
T8	3 X 18" DIA. 35' LONG	A	216+33.7	13.4 R	278.6
		B	216+01.4	13.1 R	278.1
		C	216+17.7	6.7 L	277.8

LOG TRIANGLE DETAIL 1
SCALE: AS NOTED 26

NSD CGS Natural Systems Design + Coastal Geologic Services

SKAGIT COUNTY
PUBLIC WORKS
1800 CONTINENTAL PLACE
BOZEMAN, WA 98273-8625
(360) 416-1400

NO.	REVISIONS	DATE




PROJECT NO. EC02145
DESIGNED BY: NT
CHECKED BY: [Signature]
DRAWN BY: DES
APPROVED BY: [Signature]


PROJECT LOCATED NEAR:
CONCRETE, WA
S 141734 N.R.E

CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK
CHANNEL STRUCTURE DETAILS (1 OF 3)


1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY
SHEET
26 OF 30




- BANK ROOTWAD NOTES**
1. BANK ROOTWAD LOCATIONS WILL BE STAKED BY THE ENGINEER.
 2. INSTALL 18" DIA 20' LONG LOG WITH ROOTWAD INTO CHANNEL BANK WITH ROOTWAD PROJECTING INTO CHANNEL.
 3. INSTALL 12" DIA., 20' LONG (PF-20) VERTICAL PILE INTO BANK ADJACENT TO LOG ON UPSTREAM SIDE.
 4. INSTALL 12" DIA., 20' LONG (PF-20) PILE ON A BATTER ON DOWNSTREAM SIDE OF LOG AS DIRECTED BY ENGINEER TO PIN LOG IN PLACE.
 5. FOR LOGS DOWNSTREAM OF THE CULVERT, INSTALL LOGS WITH BOTTOM OF LOGS SITTING AT THE TOE OF THE CONSTRUCTED CHANNEL.
 6. FOR LOGS UPSTREAM OF THE CULVERT, INSTALL LOGS WITH BOTTOM OF LOG 1.5' ABOVE CHANNEL THALWEG.



BANK ROOTWAD DETAIL 1
NTS 28




- CHANNEL ROOTWAD NOTES**
1. INSTALL 18" DIA LOG WITH ROOTWAD EMBEDDED INTO CONSTRUCTED CHANNEL BED. LOCATION AND ORIENTATION TO BE IDENTIFIED IN THE FIELD BY THE ENGINEER. SHORT CHANNEL ROOTWADS SHALL BE 25' LONG AND LONG CHANNEL ROOTWADS SHALL BE 40' LONG.
 2. CHANNEL ROOTWAD LOG SHALL BE ORIENTED WITH ROOTWAD FACING UPSTREAM. ROOTWAD END SHALL REST ON TOP OF OTHER LOG. CUT LOG END SHALL BE ORIENTED DOWNSTREAM AND EMBEDDED IN STREAMBED MIX BENEATH OTHER LOG AS SHOWN.
 3. INCORPORATE SLASH (2-3 CY) INTO BACKFILL OF PARTIALLY EXPOSED CHANNEL ROOTWADS AS DIRECTED BY ENGINEER.



CHANNEL ROOTWAD DETAIL 3
NTS 28


TYPE 316 3/8" STAINLESS STEEL CHAIN, MIN WORKING LOAD LIMIT 3,500 POUNDS



CROSS CHAIN LASHING NOTES


1. SECURE TAG END OF CHAIN TO TOP LOG TEMPORARILY USING A RAILROAD SPIKE, LARGE FENCING NAIL, OR SIMILAR.
2. WRAP THE CHAIN FULLY AROUND THE BOTTOM LOG THEN ANOTHER HALF WRAP AROUND THE UNDERSIDE OF THE BOTTOM LOG. THEN CROSS OVER THE TOP LOG DIAGONALLY.
3. WRAP CHAIN FULLY AROUND THE BOTTOM LOG THEN ANOTHER HALF WRAP AROUND THE UNDERSIDE OF THE BOTTOM LOG.
4. PULL CHAIN BACK TO THE TAG END SECURED TO THE TOP LOG.
5. SQUARE UP ALL WRAPS AND LOOPS TO REMOVE SLACK PRIOR TO TENSIONING.
6. APPLY TENSION TO THE CHAIN USING MECHANICAL MEANS (CHAIN BINDER, OR SIMILAR). WHILE CHAIN IS FULLY TENSIONED, APPLY QUICK LINK TO CHAIN WHILE TENSIONED THEN SLOWLY RELEASE TENSION.
7. TRIM EXCESS CHAIN.

CROSS CHAIN LASHING DETAIL 2
NTS 28



TIMBER HANDRAIL NOTES:

1. TIMBER HANDRAIL SHALL BE CONSTRUCTED FROM PRESSURE TREATED (GROUND CONTACT RATED) NOMINAL LUMBER.
2. EMBED TIMBER POSTS A MINIMUM OF 2 FEET BELOW THE EXISTING GROUND SURFACE.
3. PITS FOR POSTS SHALL BE NEATLY CREATED, FREE OF DEBRIS AND WATER, AND SHALL MEET THE MINIMUM DIMENSIONS SHOWN ON THIS SHEET.
4. BACKFILL PITS FOR POSTS WITH CONCRETE (MINIMUM 3,000 PSI COMPRESSIVE STRENGTH) AND SHALL HAVE A SLOPING MINIMUM OF 1" ABOVE GROUND.
5. ALLOW CONCRETE TO CURE A MINIMUM OF 24 HOURS PRIOR TO ATTACHING RAILS.
6. CONNECT RAILS TO POSTS WITH GALVANIZED FACE MOUNTED JOIST HANGERS AND MANUFACTURER RECOMMENDED NAILS OR SCREWS.
7. ALL POSTS AND RAILS SHALL BE SIMILAR IN APPEARANCE.



TIMBER HANDRAIL DETAIL 4
NTS 28



Natural Systems Design
+ Coastal Geologic Services

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
SEASIDE, WA 98274-5625
(360) 416-1400

NO.	REVISIONS	DATE





PROJECT NO. EC02145
DESIGNED BY: JNT
CHECKED BY: JNT
DRAWN BY: DES
APPROVED BY: JNT
PROJECT LOCATED NEAR:
CONCRETE, WA
S 14 T 34 N R 8 E



CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK
CHANNEL STRUCTURE DETAILS (3 OF 3)

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY

SHEET
28 OF 30



PLANTING AREA LEGEND

-  SLOPE PLANTING AREA (SP)
-  TERRACE PLANTING AREA (TP)

NOTES:

1. FOLLOWING COMPLETION OF EARTHWORK AND STRUCTURE PLACEMENT, ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED ACCORDING TO SHEET B.
2. PLANTING SHALL OCCUR FOLLOWING SEEDING ACCORDING TO THE AREAS SHOWN THIS SHEET AND THE SCHEDULES LISTED ON SHEET 30.
3. PLANTING BOUNDARIES SHOWN ON THIS SHEET ARE THE EXPECTED LIMITS OF DISTURBANCE RESULTING FROM THE SOUTH OSTERMAN CREEK PROJECT AND MAY VARY AT THE TIME OF PLANTING; PLANTING BOUNDARIES AND LAYOUT SHALL BE APPROVED BY THE ENGINEER PRIOR TO COMMENCEMENT OF WORK.
4. PLANTING SHALL OCCUR AROUND EXISTING STRAW MATTLIES, PLACED AS SHOWN ON SHEET B. STRAW MATTLIES SHALL REMAIN.
5. NO PLANTING SHALL OCCUR WITHIN 10' OF THE FINISHED EDGE OF PAVEMENT.



Natural Systems Design
+ Coastal Geologic Services

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
BELLINGHAM, WA 98275-8625
(360) 416-1400

NO.	REVISIONS	DATE



COUNTY ENGINEER

PROJECT NO. EC20245	DESIGNED BY: NT	DRAWN BY: DES
FIELD NO. 46020245R1660	CHECKED BY:	APPROVED BY:
PROJECT LOCATED NEAR: CONCRETE, WA S 141734 N 18 E		

**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**

PLANTING PLAN

1 INCH SCALE BAR
ADJUST SCALE ACCORDINGLY


SHEET
29 OF 30

SLOPE PLANT SCHEDULE							AREA QUANTITIES				
PLANT TYPE	ID	SPECIES NAME	COMMON NAME	TYP. SPACING	SIZE	TOTAL QUANTITY 0.33 AC	SP1 2584 SF	SP2 1136 SF	SP3 7060 SF	SP4 3725 SF	
TREE											
	ACMA	ACER MACROPHYLLUM	BIGLEAF MAPLE	8'	1 GAL	12	2	1	6	3	
	ALRU	ALNUS RUBRA	RED ALDER	8'	1 GAL	12	2	1	6	3	
	CRDO	CRATAEGUS DOUGLASII	BLACK HAWTHORN	8'	1 GAL	12	2	1	6	3	
	PSME	PSEUDOTSUGA MENZIESII	DOUGLAS-FIR	8'	1 GAL	23	4	2	11	6	
	SALA	SALIX LASIANDRA	PACIFIC WILLOW	3'	4' LIVE STAKE	161	29	13	78	41	
SHRUB											
	ACCI	ACER CIRCINATUM	VINE MAPLE	6'	1 GAL	40	7	3	20	10	
	COCO	CORYLUS CORNUTA	BEAKED HAZELNUT	6'	1 GAL	21	4	2	10	5	
	COSE	CORNUS SERICEA	REDOSIER DOGWOOD	4'	1 GAL	90	16	7	44	23	
	OECE	OSMELERIA CERASIFORMIS	OSOBERRY	4'	1 GAL	46	8	4	22	12	
	RIDI	RIBES DIVARICATUM	SPREADING COOSEBERRY	4'	1 GAL	46	8	4	22	12	
	RUPA	RUBUS PARVIFLORUS	THIMBLEBERRY	4'	1 GAL	46	8	4	22	12	
	RUSP	RUBUS SPECTABILIS	SALMONBERRY	4'	1 GAL	90	16	7	44	23	
	SYAL	SYMPHORICARPOS ALBUS	SNOWBERRY	4'	1 GAL	46	8	4	22	12	
GROUND											
	ARUV	ARCTOSTAPHYLOS UVA-URSI	KINNICKINICK	3'	4"	80	14	6	39	21	
	ACMI	ACHILLEA MILLEFOLIUM	COMMON YARROW	3'	1 GAL	80	14	6	39	21	
						TOTAL QUANTITIES	805	142	65	391	207


TERRACE PLANT SCHEDULE							AREA QUANTITIES			
PLANT TYPE	ID	SPECIES NAME	COMMON NAME	TYP. SPACING	SIZE	TOTAL QUANTITY 0.24 AC	TP1 4073 SF	TP2 1411 SF	TP3 1101 SF	TP4 4037 SF
TREE										
	ACMA	ACER MACROPHYLLUM	BIGLEAF MAPLE	8'	1 GAL	16	6	2	2	6
	PSME	PSEUDOTSUGA MENZIESII	DOUGLAS-FIR	8'	1 GAL	25	10	3	3	9
	THPL	THUJA PLICATA	WESTERN RED CEDAR	8'	1 GAL	16	6	2	2	6
SHRUB										
	ACCI	ACER CIRCINATUM	VINE MAPLE	6'	1 GAL	29	11	4	3	11
	SARA	SAMBUCUS RACEMOSA	RED ELDERBERRY	6'	1 GAL	45	17	6	5	17
	SYAL	SYMPHORICARPOS ALBUS	SNOWBERRY	4'	1 GAL	66	25	9	7	25
GROUND										
	MAAQ	BERBERIS AQUIFOLIUM	TALL OREGONGRAPE	4'	1 GAL	99	36	13	10	38
	POVU	POLYSTICHUM MUNITUM	WESTERN SWORDFERN	3'	1 GAL	177	68	24	18	67
						TOTAL QUANTITIES	473	181	63	179

GENERAL NOTES:

- SEE SHEET 29 FOR PLANTING AREA LOCATIONS.
- TYPICAL SPACING INDICATES MINIMUM PLANTING DISTANCE BETWEEN LIKE SPECIES. PLANTS SHALL BE EVENLY SPACED ACROSS THE PLANTING AREA SUCH THAT ALL PLANTING AREAS ARE EVENLY COVERED.
- IF SUFFICIENT QUANTITIES OF PLANT MATERIALS ARE NOT AVAILABLE IN THE SIZES SPECIFIED, THE CONTRACTOR MAY SUBSTITUTE MATERIAL IN EQUIVALENT OR GREATER SIZE, AS APPROVED BY THE ENGINEER.
- LIVE STAKES SHALL BE PLANTED LANDWARD OF THE CREEK, WITHIN 5' OF THE CONSTRUCTED TOP OF BANK.
- EXISTING WOOD CHIP MULCH SHALL BE REFRESHED FOLLOWING PLANTING ACTIVITIES, AS DIRECTED BY THE ENGINEER. FINISHED MULCH PLACEMENT SHALL BE MIN. 3" DEPTH AND SHALL NOT EXCEED 8" DEPTH, TAPER MULCH NEAR BASE OF EACH PLANT TO ENSURE MULCH DOES NOT MAKE CONTACT WITH PLANT STEMS. WOOD CHIP MULCH SHALL NOT BE PLACED WITHIN 3" OF THE PLANT STEM.



LIVE STAKE DETAIL 1
NOT TO SCALE 30



BARE ROOT AND CONTAINER PLANTING DETAIL 2
NOT TO SCALE 30

**SKAGIT COUNTY
PUBLIC WORKS**
1800 CONTINENTAL PLACE
SEASIDE, WA 98274-8625
(360) 416-1400

NO.	REVISIONS	DATE




COUNTY ENGINEER

PROJECT NO. EC20245	DESIGNED BY: NT	DRAWN BY: DES
FED. AID NO. 865004N-016835	CHECKED BY:	APPROVED BY:
PROJECT LOCATED NEAR: CONCRETE, WA S 141734 N 18 E		

**CONCRETE SAUK VALLEY ROAD
CULVERT REPAIR PROJECT -
SOUTH OSTERMAN CREEK**

PLANT SCHEDULES & DETAILS



NE - September 25, 2025 - 2:45 PM - P:\A\GDA\EVANS AND ASSOCIATES\SOUTH_OSTERMAN_CONSTRUCTION_SUPPORT_DEA\1702583\NCAD DWG\PLANTING PLANDWG